

19-27-23W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - THE TEXAS COMPANY

Farm - E. N. Davis

No. 11

SEC. 19 T. 27 R. 23W

SW SW SE

Total Depth. 6056'

Comm. 6-25-48

Comp. 8-19-48


Shot or Treated.

Contractor. Herndon Drilg. Co.

Issued. 10-2-48

County. Ford

KANSAS

Elevation. 2477' *ind.*

Production. Dry

CASING:

13-3/8" 313' Cem. W/300 Sx.

9-5/8" 1536' Cem. W/350 Sx.

Figures Indicate Bottom of Formations.

sand	250	Plugged W/heavy mud from 6056-1540
sand & shela	314	Plugged W/ 20 sx. cem. from 1540-1488
sand	550	Plugged W/heavy mud from 1488-300
lime & sand	665	Plugged W/ 30 sx cem. from 300-270
sand	765	Plugged W/ heavy mud from 270-34
red bed	1050	Plugged W/20 sx cem. from 39- Top.
shale & shells	1430	
anhydrite	1386	
shale	1536	
shale & sand	1825	
sand & shale	1982	
shale	2192	
lime & shale	2490	
lime	2838	
lime & shale	3175	
lime	3420	
lime & shale	3500	
lime	5005	
lime & chert	5188	
lime	5378	
shale	5410	
lime & chert	5568	
chert	5582	
lime & chert	5704	
lime	5744	
lime & chert	5808	
lime	5878	
lime & chert	5898	
lime	6056	
Total Depth		

Tops:

Stone Corral	1434
Herington	2590
Winfield	2674
Ft. Riley	2790
B. Florence	2889
Wreford	2940
B. Wreford	2988
Grenola	3147
B. Americus	3346

Topok	3786
Neohor	4250
Lanning	4294

7-22-48 - Ran DST #1, packer

Set at 4416' W/30' anchor,
open 1 hr, hole filled up 3000'
W/salt wtr.

7-30-48 - Took DST #2, packer at 5019' W/21'
anchor, open 1 hr., good blow of gas,
75' rotary mud.

8-15-48 - Ran DST #3 from 5870'-78', open
1 hr., rec. 20' mud, no show oil or gas.

8-16-48 - Cored from 5378- 85', rec. 2' wh sand,
6" gy shale & 4' fine granulated brwn dolo.

8-17-48 - Ran DST #4, packer at 5047' W/9' anchor,
open 1 hr, 540' salt wtr.

8-18-48 - Plugged & Abandoned