

35-27-24W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company. THE TEXAS COMPANY
Farm. L.L. Barngrover No. 1

SEC. 35 T. 27 R. 24W
SW NW NE

Total Depth. 6172'
Comm. 6-17-47 Comp. 8-10-47
Shot or Treated.
Contractor. Herndon Drilling Company
Issued. 10-18-47

County. Ford
KANSAS



Elevation. 2528' set 4 rh

CASING:

13" 390' Cem. w/500 sx
9-5/8" 1509' Cem. w/350 sx

Production. Dry

Figures Indicate Bottom of Formations.

sand & shale 390
shale 860
red bed 1010
lime 1030
shale 1115
lime brkn 1140
shale 1250
red bed 1305
shale & red bed 1450
red bed 1510
lime 1520
red bed & lime 1540
lime 1550
shale 2045
salt & shale 2165
shale 2335
shale & lime strks 2460
lime 2780
lime & chert 2800
lime 3000
shale & lime 3590
lime 3605
lime & shale 3620
lime 4180
lime & shale 4440
lime & chert 4490
lime, shale & chert 4594
lime & chert 4605
lime & shale 4670
lime 4705
lime & shale 4750
lime & chert 4780
lime & shale 4800
lime, chert & shale 4830
lime & shale 5040
lime 5069
lime & chert 5083

Tops:
Anhydrite 1500
Fort Riley 2842
Lansing 4350
Mississippi 5070
Viola 5800
Simpson 5920
Arbuckle 5954

Remarks:

7-20-47 Ran DST, Packer didn't hold.
8-9-47 Ran DST 6100-6125, Packer at 6100, open 45 min., filled up 2760 w/ salt water.
8-13-47 Shot 9-5/8" csg at 504-446-414-382. Pipe came loose at 382 but would only pull 18". Cir. to get loose and finish plugging.

lime 5095
lime & chert 5110
lime sdy 5115
lime 5180
lime & chert 5280
lime 5545
lime & chert 5710
lime 5840
lime sdy & chert 5875
lime sdy 5950
sand & shale 5975
lime 6172
Total Depth