

IMPORTANT
Kans. Geo. Survey request
same as usual. All wells well.

CONFIDENTIAL CUSTODY *Jnd*
As allowed under Rule 82-2-125

CONFIDENTIAL

S. 16 T. 27S R. 29 E W

Loc. SE SE NW

County Gray

640 Acres


API No. 15 — 069 — 20,075
County Number

Operator
Pendleton Land and Exploration, Inc.

Address
23 Inverness Way East - Englewood, Colorado 80112

Well No. 1 Lease Name Fry "B"

Date: JUN 4 1980



Footage Location
2310 feet from (N) line 2310 feet from (W) line

Principal Contractor Silverado Rig #8 Geologist Bill Ree

Spud Date 6-7-80 Total Depth 5200' P.B.T.D.

Date Completed 6-20-80 Oil Purchaser

Locate well correctly
Elev.: Gr. 2745'
DF KB 2756'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	24#	1820	lite Class H	800 200	2% gel, 2% cc 3% cc

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Plugged: @ 1800' w/ 50 sx	
@ 900' w/ 25 sx	
@ 40' w/ 10 sx, 5 sx in rat hole	

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)				
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator
Pendleton Land and Exploration, Inc.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Well No. 1 Lease Name Fry "B" Dry Hole

S 16 T 27 S R 29 W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 4268-4325 30"45"30"60" REC 185' IFP 93-93, ISIP 1053 FFP 105-129, FSIP 1100				
DST #2 4325-47 30"45"60"60" Rec 60' GIP 125' OCM SLGC IFP 30-105 ISIP 1041 FFP 60-117, FSIP 528'				
DST #3 4370-85 30"45"60"60" Rec 430' IFP 30-58, ISP 1227, FFP 60-117, FSIP 1204				
DST #4 4401-11 40"45"30"60" Rec 2' SI Ospkd M IFP 23-23 ISIP 58, FFP 23-23 FSIP 35				
DST #5 4402-17 30"45"60"60" Rec 95' GIP 25' MO 720 0 & GCW 1945 SW IFP 410-1134, ISIP 1227, FFP 1193-1239 FSIP 1251				
			Heebner	4117
			Toronto	4134
			Douglas Shale	4154
			Lansing	4208
			BKC	4592
			Marmaton	4610
			Pawnee	4768
			Ft Scott	4792
			Cherokee	4807
			St Gen	4966
			St Louis	5048
			Log: DIL, CNL, FDC, FR, BHC, GR.	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Lee Brian VanRamsdorf

Lee Brian VanRamsdorf
Manager of Operations

Title

June 11, 1981

Date