

KANSAS DRILLERS LOG


API No. 15 — 081 — 20,064
County Number

S. 9 T. 27S R. 31 W

Loc. SW NE

County Haskell

640 Acres
N



Locate well correctly
Elev.: Gr. 2802.74'

DF KB

Operator
Anadarko Production Company & Diamond-Shamrock Corporation

Address
P. O. Box 351, Liberal, Kansas 67901

Well No. 1 Lease Name Bedell "A"

Footage Location
1980 feet from (N) (3/4) line 1980 feet from (E) (3/4) line

Principal Contractor Geologist
Gabbert-Jones, Inc.

Spud Date Total Depth P.B.T.D.
7-28-75 5216'

Date Completed Oil Purchaser
8-12-75

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Socks	Type and percent additives
Surface	12-1/4"	8-5/8"	20#	695'	Common	550	3% CC
Production	7-7/8"	4-1/2"	10.5#	5214'	Pozmix	200	.1% CFR-2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Socks cement	Shots per ft.	Size & type	Depth interval
			2 SPF		5048'-5066' OA
			2 SPF		5004'-5008'

TUBING RECORD

Size	Setting depth	Packer set at	Shots per ft.	Size & type	Depth interval
2-3/8"	5019'	5030'	2 SPF		5004'-5008'

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidized w/2500 gallons 15% + 30 ball sealers. Fraced w/15,000 gallons gelled 1% KCL water + 15,000# 20-40 sand.	5048'-5066' OA

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
8-30-75		Pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	134 bbls.	47 MCF		351 CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		
Vented			5004-08' Morrow		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator
Anadarko Production Company & Diamond-Shamrock Corporation

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Well No.
1

Lease Name
Bedell "A"

Oil

S 9 T 27 S R 31 ^X W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Sand	0	251		
Blue Clay	251	700		
Blue Clay-Redbed	700	1114		
Redbed-Sand	1114	1240		
Sand	1240	1550		
Shale-Shells-Lime	1550	1926		
Shale-Lime	1926	2020		
Shale-Lime Stks	2020	2295		
Lime-Shale	2295	2825		
Sand-Lime	2825	2838		
Lime-Shale	2838	5084		
Lime	5084	5087		
Lime-Sand-Shale	5087	5118		
Lime-Shale	5118	5216		
Total Depth		5216		
DST #1 2565-2662' (Krider), open 20 min, SI 45 min, open 40 min, SI 80 min w/weak to fair blow, REC 30' drilling mud. ISIP 86# (45), IFP 27-34, FP 34-34#, FSIP 428# (80).				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

J. W. Smith
J. W. Smith
Signature
Division Production Manager
Title
September 11, 1975
Date