

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY CITIES SERVICE OIL CO.


FARM Atkins "H" NO. 1

SEC. 3 T. 27 R. 33W

LOC. NE NE SW
100' S. & 100' W.
of Center

COUNTY Haskell

KANSAS



TOTAL DEPTH 2790'

COMM. 10-18-49

COMP. 10-24-49

SHOT OR TREATED

CONTRACTOR Corbett & Barbour Drlg. Co.

ISSUED 6-2-51

CASING

8 5/8" 760' cem w/325 sx.s.
5 1/2" 2789' cem w/700 sx.s.

ELEVATION 2926

PRODUCTION 12,800,000 gas

FIGURES INDICATE BOTTOM OF FORMATIONS

clay & sand	110
sand & gravel	220
shale & shells	650
sand & shells	700
shale & shells	760
shale & red bed	1500
shale & shells	2320
anhydrite & shale	2485
shale & lime	2595
anhydrite & shale	2670
lime & shale	2790
Total depth	

Tops:	
Herington	2591
Upper Krider	2619
Lower Krider	2642
Winfield	2687
Upper Ft. Riley	2720

Perforated:

80 shots	2620-36
80 shots	2644-60
90 shots	2680-98
40 shots	2730-38
20 shots	2744-48
60 shots	2754-66

SIP 409.5