

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas


9-27-34W

Company - WHITE EAGLE OIL CO.
Farm - Jones No. 14

SEC. 9 T. 27 R. 34W
SE SE NW
2310' EWL 330' NSL of NW/4

Total Depth. 2700
Comm. 8-28-48 Comp. 9-9-48
Shot or Treated.
Contractor.
Issued. 2-4-50

County. Haskell
KANSAS



Elevation. 2980 Ind.

Production. 10,852,000 gas

CASING:

10 3/4" 522' cem. w/400 sx.
7" 2507' cem. w/750 sx.

Figures Indicate Bottom of Formations.

clay & sand	480
shale blue	730
red bed	985
red bed & gyp	1150
red bed	1220
anhyd.	1295
red bed	1650
anhyd. & red bed	1680
red bed	1790
anhyd. & shale	1830
anhyd. & lime	1900
anhyd. & red bed	1945
red bed	2140
anhyd. & shale	2235
lime & shale	2295
lime	2390
anhyd., shale & lime	2480
lime	2558
shale	2568
lime br n	2590
lime	2606
shale	2615
lime	2700
Total Depth	
Tops:	
Herington	2509-2520
Krider	2523-2545
Winfield	2563-2589
Upper Fort Riley	2611-2652
Lower Fort Riley	2664-2700

Acidized w/13,000 gals of 15% & 4,000 gals
7 1/2% acid.

Rotary total depth 2553