

COPY RELEASED

1-27-34W



Natural Gas • Crude Oil
Exploration & Production

OCT 07 1992

KCC

FROM CONFIDENTIAL SEP 19

CONFIDENTIAL

McCOY PETROLEUM CORPORATION

110 South Main, Suite 500
Wichita, Kansas 67202

Computer Inventoried

316-265-9697

John Roger McCoy
President

Kevin McCoy
Vice-President

Harvey H. McCoy
Vice-President

Keith McCoy
Treasurer

APL # 15-081-20704

Schroeder "A" #1-1
50' NE of C SW SW SE
Section 1-27S-34W
Wildcat
Haskell County, Kansas

Page 2 (ACO-1)

DST #1 4600-4665' (Marmaton "B")

Open 30", S.I. 60", Open 60", S.I. 90"
Weak blow increased to strong blow on 1st open.
Weak blow increased to strong blow on 2nd open.
Recovered 5' of mud with a show of oil,
720' of muddy salt water (72,000 ppm).
FP 72-203# 230-373#
ISIP 1360# FSIP 1337#

DST #2 5038-5138' (Morrow)

Open 30", S.I. 60", Open 30", S.I. 60"
Weak blow, died in 20" on 1st open.
Weak blow, died in 1" on 2nd open.
Recovered 15' of mud.
FP 49-49# 49-49#
ISIP 72# FSIP 67#

DST #3 5230-5258' (Chester Sand)

Open 30", S.I. 60", Open 60", S.I. 120"
Weak blow throughout 1st open period.
Weak blow, died in 12 minutes on 2nd open period.
Recovered 15' of oil cut mud, (5% oil, 95% mud).
FP 49-56# 67-72#
ISIP 696# FSIP 1016#

ELECTRIC LOG TOPS

Winfield	2674 (+ 313)
Council Grove	2894 (+ 93)
Heebner	3984 (- 997)
Lansing	4030 (-1043)
Marmaton "A"	4636 (-1649)
Marmaton "B"	4656 (-1669)
Cherokee	4773 (-1786)
Atoka	4993 (-2006)
Morrow Shale	5055 (-2068)
Chester Sand	5246 (-2259)
St. Genevieve	5272 (-2285)
St. Louis	5304 (-2317)
LTD	5458 (-2471)

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 19 1991

CONSERVATION DIVISION
WICHITA, KS