

FORMATION TOPS

27 27 34W NE NE SW
 Sec. Twp. Rge. Location

Haskell Kansas 3038
 County State Elevation

Cities Service Oil
 Company

Her. 2568
 U.K. 2597
 L.K. 2620
 Winf. 2660
 U.F.R. 2702
 L.F.R. 2726

1 Alexander "C"
 Well No. Farm

100 N Line
 Feet from of SW/4
100 E Line
 Feet from

CASING
8 5/8" 800 (325)
5 1/2" 2854 (700)

| | | | | | | | |
|--|--|--|--|--|--|--|--|
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

Producing Formation
 T. D. 2855 I. P. 6.140M

Date Sp. 8-12-47.

R.T.D. 2855. RUST C.O. Perf. 60 holes 2788-2800;
 Perf. 30 holes 2768-74. A/1000 gals., 24 hr. B.D.
 416MCF. Perf. 89 holes 2722-40, 458MCF; Perf. 96
 holes 2678-98, no inc.; Perf. 50 holes 2658-68, no
 inc. A/500 gals. 2658-68; A/1350 gals. 2678-98;
 A/1150 gals. 2722-40. 24 hr. B.D. 1.240M. A/9500
 gals. 2658-2740; A/3500 gals. 2788-2800. 20 hr. B.D.
 2.330M. 56 hr. B.D. 2.240M & 1 gal. salt wtr. in
 2 min.; 104 hr. B.D. 1.830M & 3 gal. salt wtr. 7 min.
 P.B. 2796 with plastic. B.D. 1.360M & 3 gal. salt
 wtr. in 7 min. wtr. decreasing. I.P. 6.140M

R.P. 387.7#

Del 623 MCF

RP 404*

¢
 OCT 21 '47