


State Ks. Field Pl. Prairie ^{stop out}
 Company White Eagle County Haskell
 Farm Jones No. 0-32
 Sec. 9 Twp. 27.5 Range 34W

Spot 60's of C SW NW

Contractor C. T.

Remarks P.O. 5200



Comm. 12/26/58 Comp. 4/15/59

Elev. DF 2990 GL KB TD 5155 PB

Pay St. L. 5052-66, 5094-5102
P 3891-99 (gas for lift)

I.P. F 72 BOPH Press.

Casing Record: 13³/₈ 95/450 7" 5154/600
 20" 10³/₄ 780/150 5¹/₂"
 16" 8⁵/₈

	Sample	Log
spud, @ TTD 720	Top 3410	Top 3412
w/ L.C.	Hb 3847	Hb 3845
JAN 7 log <u>LC @ 930</u>	Top 3860	Top 3860
φ 23 60	Lon 3891	Lon 3891
JAN 14 <u>E 3862-78</u>	Mtm 4498	Mtm 4498
rec 16' ls gd per 50	st. G.	Cher 4650
<u>E 3878-3912</u>	Cher 4650	Atk 4863
rec 34' 4' ls, 4' sh,	Atk 4863	Wor ⁻¹⁹³² 4922
12' ls li per sso, 14' ls	Mar 4922	st. G. ⁻²⁰²⁴ 5014
1.1 ft,	st. G. 5014	st. L. ⁻²⁰⁵⁴ 5042
<u>PST 3880-3916</u>	st. L. 5042	"B ₃ ⁻²⁰⁵⁵ 5045
cp 40" gts 1" g 2,930 mf	"B ₃ 5045	(15') 60
5" 4,260 mf/15"	60	"C ₃ ⁻²¹⁰¹ 5091
4,450 mf/30 sp mud/32"	C ₃ 5091	(8') 99
rec 40' sulfur wtr	99	"D ₃ ⁻²¹³⁶ 5126
gas man - commercial	"D ₃ 5126	(5') 31
<u>FP 965-900 BHP 10/20/20</u>	31	

~~φ 4389~~
 JAN 21 RTD 5155 sj. log.

WOCT.
 JAN 28 MI 60? P32/5094-5102
A/1000 sub 1/2 BOPH, P 56/5052-66
sub 2 BOPH Fx 25 x 50' d screen-out

613970

CO sd.

FEB 4 CO all sd pl @ 5080 A/1000 (15%)

+ 12,600 (5%) swbg.

FEB 11 sub all lcl T. fx 10 days x 10 sd.

sub all lcl subd 10 BOPH/4'

pull T + apr + ret. pl. to install

FEB 18 ~~gas lift equip.~~
P 16/3891-99 (gas will be used
for gas lift)

FEB 25

MAR 4

MAR 11

MAR 18

MAR 25

APR 1

APR 8

st-tst, 72 BOPD (not submitted)

APR 15

st. l. 5052-66

5094-5102

gas fm 3891-99 used for gas lift

AMARILLO TOPS

2991 KB

Winfield 2573 (+418)

Heebner 3850 (-859)

Lansing 3888 (-897) Tst'd 4,400 MCF \neq XW

Marmaton 4496 (-1505)

Morrow 4923 (-1932) T' 91', no ss

St. Gen 5014 (-2023)

St. Louis "A" 5040 (-2049) 12' por/
"B" 5091 (-2100) 8' por / \neq 72 BOPD

"C" 5130 (-2139) 8' por