

FORMATION

TOPS

3

27

34W

NE SW SE

Sec.

Twp.

Rge.

Location

Haskell

Kansas

2998

County

State

Elevation

Helmerich & Payne

Company

Her. 2600

Kri. 2616

Winf. 2652

U.F.R. 2705

10

Jones

Well No.

Farm

Line

Feet from

Line

Feet from

CASING

10 3/4" 568 ()

7" 2600 ()

152' of 5 1/2" lnr.

on Bottom PBD 2720

Producing Formation

T. D.

2779

I. P.

6.440M

Date

Sp. 2-26-48.

R.T.D. 2610. RUST D.D. T.D. 2779. A/12,000 gals.,

show wtr. P.B. 2740. Ran 194' of 5 1/2" lnr. on Bott.

72 hr. B.D. 1.672M & spray wtr. 72 hr. S.I., 20

min. B.D. 4.630M Del. 606Mcf. R.F. 403#. Pulled.

lnr. Temp. P.B. 2716 w/ sand & plastic. Temp. P.B.

2682. Shot 120 qts. 2652-82. Temp. P.B. 2640. Shot

96 qts. 2616-40. C.O. to 2720. Ran 152' of 5 1/2" lnr.

to 2720. A/10,000 gals. I.P. 6.440M dry.

R.P. 404#

JUN 14 49