


State Ks. Field Pl. Prairie
 Company White Eagle County Haskell
 Farm Devlin - Jones (4-5) No. X-5
 Sec. 4 Twp. 27S Range 34W

Spot C SW SE
 Contractor C.T.



Remarks P.D. 5200 st. l.

Comm. 12/2/58 Comp. 3/25/59
 Elev. LTS DF 2990 GL 2982 KB TD 5209 PB 5160
 Pay st. l. 5066-82, 5148-56

9x34.30
 I.P. F 102 BOPD Press.
 Casing Record: 13 3/8 on gas lift 7"
 20" 10 3/4 5 1/2" 5208/650
 16" 8 5/8 798/550

Loc.	Sample	Log
DEC 3 <u>spudding</u>		Top 3478
DEC 10 <u>org. 3115</u>		Hb 3909
DEC 17 <u>4410</u>		Top 3926
DEC 30 <u>E 5065-5115</u>		Lat 3953
rec 50' 2'ls, 10' oöls		B/KC 4539
60. 4'ls sd. lam.		Marm 4560
20' sdy ls, 14'ls		Chero 4704
E 42 5116-65 rec 49'		Atk 4911
16'ls sdy, 11'ls sd lam		Mor ⁻¹⁹⁸⁰ 4970
spotty oil sta, 5'ls g so		st. l. ²⁰⁷³ 5063
16'ls tite,		B-B ²⁰⁷⁶ 5066-
RTD 5209 logs.		(15) 81
<u>org. MICT</u>		²¹⁵⁹ C ₃ 5149-
JAN 7 <u>MICRU CO 5160 G/R</u>		(6) 50
P 16/ 5148-56 A/1000 m		D ₃ ⁻²¹⁹³ 5183-
sub 128 G OPH no wtr / 8'		(7) 90
FR 10 oil x 9 ad sub 1d + 26 BOPH		
no wtr / 14' pl 5100 P 32/ <u>5066-82</u>		
<u>try to swab.</u>		
JAN 14' <u>sub N.S. A/1000 sub</u>		
8 BOPH Fx 15 (52 A.) x 42 ad.		
sub 8 BOPH & pl CO 5160		
<u>tsq.</u>		

614251

JAN 21 sub. 20 BOPD month 14' rmg T.
to make gas lift, in 0-32 Jones.
in ~~the~~ 9-275-34W

JAN 28 FEB 4 FEB 11 FEB 18
FEB 25 MAR 4 MAR 11 MAR 18

MAR 25 St. 1st F102 BOPD

gr 34.3

St. L. 5066-82

5148-56

⌘

AMARILLO TOPS

2991 KB

Winfield 2627 (+364)

Heebner 3913 (-922)

Lansing 3951 (-960)

Marmaton 4558 (-1567)

Morrow 4972 (-1981) T 89', no SS

St. Louis "A" 5061 (-2070) 16' por / IPF 162 BOPD (on gas lift)
" " "B" 5146 (-2155) 8' por
" " "C" 5183 (-2192) 9' por