

4-95W


(Pleasant Prairie) (55)

MAP NO. K-78 SEC. 4 TWP. 27S RGE. 34W
 STATE Kans COUNTY Haskell LOC. App C NE NE
 OPERATOR Helmerich & Payne Inc 660 FT. FROM N LINE
 WELL NO. 23J FARM NAME USA Unit (US Jones) 600 FT. FROM E of sec LINE
Pleasant Prairie ELEV. _____ GR _____ DF 2973 KB
 FR. 12/5/61 SPUD. 12/2/61 COMP. 4/17/62

CONT. Graham-Michaelis Tools /GEOL. _____

NAME PRODUCING INTERVAL COMPLETION RECORD FROM - TO PERF. W/MOLES TREATMENT RECORD
M ss 5002-5131 82 2500A frac

b _____
 c P
 d _____



d I. P. OIL/DIST. 33 BO WTR. 2 BW GAS _____ M.C.F.P.D. _____ CHK. _____ HRS. 24
 b " " " " " "
 c " " " " " "
 d _____

SIB# _____ FI TP # _____ FI CP# _____ SIBHP _____

GOR. _____ GR. 33 deg PBTD 5180 TD 5185

SIZE	DEPTH	CASING - CEMENT W/SAX.	RECORD SIZE	DEPTH	W/SAX.
<u>8 5/8"</u>	<u>996</u>	<u>650</u>			
<u>5 1/2"</u>	<u>5184</u>	<u>125</u>			

OPERATOR Helmerich & Payne WELL NO. 23J USA Unit ELEV. 2973KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
KB tops & datums			Top	3474	- 501
Hb	3908		Hb	3902	- 929
Tor	3921		Tor	3920	- 947
Lans	3950		Lans	3949	- 976
RTD(St L)	5185	=2212	BKC	4508	-1535
			Marm	4530	-1557
RTD 5185. Log. 5 1/2" @ 5184 w/			Chero	4678	-1705
125 sx. MICT & CO, 20/5126-			Atoka	4886	-1913
31, (St L) No sho nat, 500A.			Morr	4936	-1963
\$ 1 BOPH, Frac (5000GO x 5000			St Gen	5008	-2035
# sd) \$ part ld, PB 5100,			St Lou	5060	-2087
30/5060-75 (St L) no sho nat,					
1000A, \$ ld, \$=no sho, Frac (20,000 GO x 20,000# sd) \$					
198 B ld, did not rec all ld, CO 5180, 16/5002-10, 16/5018-					
26 (St Gen) PB 5030. 1000A, (15%), \$ 135 BL/NT, \$ 2 BFPH, 15%					
wtr/3 hrs, Frac (10000 GO x 10000# sd) \$ ld. \$ 3 BOPH/NW/NT					
CO 5180, POP. P 47 BO + 3 BW/24 hrs, St Pot: P 33 BO + 2 BW					
24 hrs, Gr 33 deg, Miss 5002-5131.					

Cone 5052-5102 + 5110-66

COMPLETED

