

FORMATION TOPS 23 27 34W NE NE SW

Sec. Twp. Rge. Location

Haskell Kansas 3002
County State Elevation

Cities Service Oil
Company

Her. 2544 1 Brinkman
Well No. Farm

L.K. 2578

L.K. 2596 80 N Line
Feet from

Winf. 2630 of SW/4

L.F.R. 2686 100 E Line
Feet from

L.F.R. 2736 CASING
8 5/8" 778 (325)

5 1/2" 2824 (700)

Producing Formation _____
T. D. 2825 I. P. 17.000M

Date Sp. 9-7-47.

Set 8 5/8" 784 (325) & drilled to 2589 T.D. Twisted off drill pipe. Junked hole. Skidded 20' north.

Sp. 9-19-47. R.T.D. 2825. RUST C.O. to 2792.

Perf. 140 holes 2738-66, no show. A/1000 gals.,

24 hr. B.D. 1.040M. A/5000 gals. 24 hr. B.D. 2.100M

60 hr. B.D. 1.800M. Perf. 80 holes 2706-22; Perf.

40 holes 2688-96; Perf. 80 holes 2644-60; Perf. 105

holes 2596-2617; Perf. 30 holes 2582-88, 1.800M

A/1200 gals. 2582-2617. A/800 gals. 2644-60.

A/1000 gals. 2688-2722., 18 hr. B.D. 3.100M.

A/5500 gals. 2582-2617. A/3500 gals. 2644-60.

A/7000 gals. 2688-2722. 24 hr. B.D. 4.580M.

48 hr. B.D. 4.760M A/9000 gals. 5% all perfs.

24 hr. B.D. 4.840M. I.P. 17.000M R.P. 400.3#

Del. 1-5-78 MT

RP 414

NOV 11 47