

FORMATION

TOPS

34

27

34W

SW SW NE

Sec.

Twp.

Rge.

Location

Haskell

Kansas

3067

County

State

Elevation

Cities Service Oil

Company

Her. 2608-23

1

Alexander "B"

U.K. 2642-54

Well No.

Farm

L.K. 2660-82

100

S Line

Winf. 2702-22

Feet from

of NE/4

U.F.R. 2750-90

100

W Line

L.F.R. 2799-2834

Feet from

CASING

8 5/8" 800 (325)

5 1/2" 2844 ()

Producing Formation

T.D.

2845

I.P.

18.950M

Date

Sp. 7-28-47.

R.T.D. 2845. RUST C.O. to 2818. Perf. 50 holes

2640-50, no show; Perf. 60 holes 2610-22, no show.

A/1250 gals. 2610-22, thru. csg. A/1250 gals.

2640-50, thru. tub., gauged 1.240M. Perf. 190 holes

2750-88; Perf. 90 holes 2702-20; Perf. 160 holes

2660-80. A/1300 gals. 2660-80, thru. tub. A/1200 gals.

2702-20, thru. tub. A/2500 gals. 2750-88, thru. tub.

24 hr. B.D. 2.070M. 48 hr. B.D. 2.420M. A/2200 gals.

2610-22, thru. csg. A/5500 gals. 2640-80, thru. tub.

A/3300 gals. 2702-20, thru. tub. A/7000 gals. 2750-

88, thru. tub. 24 hr. B.D. 4.190M. 48 hr. B.D. 4.390M

A/12,000 gals 5% all perfs. 24 hr. B.D. 2.890M

I.P. 18.950M

R.P.

416.8M

SEP 30 '47

GEOLOGICAL 10M 11-46