

Computer inventoried

COPY

17-27-35W

OPERATOR: MOBIL OIL CORPORATION
FIELD: KS HUGOTON COUNTY: GRANT
WELL: MAUDE MEYER 3 SECTION: 17-27S-35W
API NO. 1506721008

DATE REMARKS

90 JUN 26 SPUD WELL IN @ 0715; DRLD TO 840'

90 JUN 27 CIRC PRIOR TO RUN CSG
SURVEY; TOH
WO FLOAT & EQUIP
RUN 19 JNTS CSG
WO DOWELL
CMT CSG
CUT OFF; WELD ON HEAD, NU
TIH
PRESSURE SHOE & BOP
DRLG PLUG & CMT
DRLG FR/840'-1231'
TIGHTEN SWIVEL PKG & TRIP INTO SURFACE PIPE
RIG REPAIR
RIH
DRLG FR/1231'-1357'

90 JUN 28 RIG REPAIR
DRLG FR/1420'-1986'
DRLG FR/1986'-2385'
SURVEY
TFB
DRLG FR/2385'-2950'
SURVEY
DRLG FR/1357'-1420'

90 JUN 29 C&C HOLE PRIOR TO LOG
TOH; SLM TO LOG
SHORT TRIP
LOGGING
TIH
CIRC PRIOR TO RUN CSG
LD DP & DC
RU CSG CREW
RUN CSG
CIRC
CMT CSG
ND, SET SLIPS, CUT OFF CSG
CLN PITS, RELEASE RIG

RECORDED
STAT. APP. 10/10/00
DEC 5 1990

COPY

MOBIL OIL CORPORATION

DRILLING COMPLETION SUMMARY

WELL: MAUDE MEYER 3
API: 1506721008
WELL TYPE: DEVELOPMENT

MATCH NUMBER: 901018

COORDINATES: 1250' FSL 4030' FEL
SECTION: 17-27S-35W
COUNTY: GRANT
WELL SPUDDED: 90 JUN 26
REACHED TD: 90 JUN 28
RIG RELEASE: 90 JUN 29

FIELD: KS HUGOTON
STATE: KS

GROUND ELEVATION: 3089
KB ELEVATION: 0
OBJECTIVE: CHASE
PROD. CASING DEPTH: 0

ADDITIONAL COMMENTS

D1

11/28/90

DEC 8 1990

COPY

OPERATOR: MOBIL OIL CORPORATION
FIELD: KS HUGOTON COUNTY: GRANT
WELL: MAUDE MEYER 3 SECTION: 17-27S-35W
API NO. 1506721008

DATE

90 JUN 26 CASING_OD 8-5/8" TOP_CSG 0 SHOE_DEPTH 842
CMT CMT W/285 SXS CL 'H LITE' W/65-35 .6, YIELD 1.87, WTR 10.89,
CMT SLURRY WT 12.7, TAILED IN W/155 SXS CL 'H' W/3% CC, YIELD
CMT 1.08, WTR 4.3, SLURRY WT 16.4, PREFLUSH W/20 BW, FULL CIRC,
CMT PIPE RECIP UNTIL PIPE STUCK, FLOATS HELD.

CMT

CMT

90 JUN 27 CASING_OD 5-1/2" TOP_CSG 0 SHOE_DEPTH 2950
CMT CMT W/255 SXS CL 'H LITE' W/65-35-6, YIELD 1.84, WTR 9.9,
CMT SLURRY WT 12.7, TAILED IN W/285 SXS CL 'H' W/50-50 LITE POZ,
CMT 2% GEL - 2% CC, YIELD 1.26, WTR 5.75, SLURRY WT 14.2, PRE-
CMT FLUSH W/20 BW, FULL CIRC, PPE RECIP UNTIL STUCK, FLOATS HELD

CMT

CMT

STAFF