

29-27-35W

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
508 East Murdock Wichita, Kansas


Company - COLUMBIAN FUEL CORP.
Farm - Rose Alexander "A" No. 1

SEC. 29 T. 27 R. 35W
SW SW NE
2540' from N & 2740' F WL, NE $\frac{1}{4}$

Total Depth. 2794
Comin. 3-13-51 Comp. 3-31-51
Shot or Treated.
Contractor. Stovall Drilling Co.
Issued. 8-4-51

County. Grant

KANSAS



CASING:

10 3/4" 496' cem w/250 sx.
7" 2596' cem w/600 sx.

Elevation. 3090 (m)
3088
3091 (and)

Production. 15,136,000 gas
Open Flow Capacity

Figures Indicate Bottom of Formations.

sand, clay	100
sand, gravel	350
clay sandy	451
sand	464
sand, clay	560
shale blue	785
shale blue, red bed	965
red bed, gyp	1320
red bed, shale	1536
red bed, gyp, shale	1906
anhydrite	1917
shale	1920
red bed, shale	2075
red rock, shale	2200
shale, gyp	2239
lime	2350
lime, shale	2400
shale, anhydrite, lime	2462
lime	2606 RTD

CABLE TOOLS

lime	2636
red, & blue shale	2656
lime	2680
shale red & blue	2684
shale sandy	2705
lime	2754
shale	2757
lime	2794

Total Depth

Tops: Scout.	2525
Hollenberg	2574
Herington	2612
Krider	2636
Winfield	2705
Upper Ft. Riley	2705
Lower Ft. Riley	2762

5 1/2" OD Liner perforations

Tops	Bottom	
2589-	2612	Blank
2612-	2636	Perforated
2636-	2656	Blank
2656-	2680	Perforated
2680-	2705	Blank
2705-	2754	Perforated
2754-	2757	Blank
2757-	2794	Perforated

5 1/2" liner set @ 2589

FT. & ins. blank 48'
" " perf. 157'

Producing sand and thickness
of each: 2612-36; 2656-80;
2705-54; 2757; 94.

This well was drilled to a TD
of 2794, acidized w/15000 gals.
bringing open from from 1,075
mcf/day to 15,136 mcf/day.