

90014

12-214W Map No. 78 O W W O
 OPER ROCK ISLAND OIL & REFG CO. - Wichita,
Ks.

S-T-R 36-27S-35WSPOT C SE SECO GRANT (Ks)ELEV 3070 KBWELL #1 APPLEMAN (Twin)

Wakefield Drlg.

FIELD Pollyana Pool (LKc Oil)*P. P 252 BOPD & tr wtr, Gr 30.9°, Tor 4046-50New Oil Pay in Pollyana Field (Lans)

(KB Spls:)

Hb 3997 - 927

Tor 4010 - 940

Lans 4085 - 1015

RTD 4133 - 1063

DDTD 4136 - 1066

OLD INFO: (Same Operator) (Spd 4-28-65 7" @655' w/265 Sx.)
 (Doug Marden - Geol)

DST #1 (Tor) 4018-4036, Op 2 hrs, R 15' Oil & 186' SOCMSW &
 324' MSW, ISIP 1068#/60", FP's 77#-230#, FSIP 1068#/60"

DST #2 (Tor) 4046-53, Op 2 hrs, & 5", 2300' GIP, R 1120' CO
 160' MO & 20' MCOC filt wtr (Tor new zn) ISIP 1061#/45"

FP's 150#-510#, FSIP 1016#/45"

DST #3 (Lans) 4092-4105, Op 60", R 10' WCM, ISIP 992#/30",
 FP's 15#-21#-, FSIP 916#/30"

DST #4 (Lans) 4109-22, Op 2 hrs, R 1350' OCSW & 882' SOCSW
 ISIP 1068#/45", FP's 429#-1008#, FSIP 1063#/45", RTD

4133, Log, 4" @4132' w/100 Sx.

CO & DD 4136 TD, 500A, § 1d, § 16 BOPH/NT, POP, P 100

BOPD & 42% wtr, OH, Lans 4132-36, Gr NA - Comp 7-26-65

Con't

Data Inc

NEW INFO: (12-9-65)

Original Lans zone still productive - 4132-36, MICT, CO Set
 Temp Plug, Est 4175, Pf 16/4046-50 (Tor) No Tests, Nat,
 500A, § 1d, § tests, NA, POP, State Pot: P 252, BOPD / tr
 wtr, Gr 30.9 deg, Tor 4046-50 (New Oil Pay in Pollyana
 Field (Lans) (Lansing zone plugged off) - FIRST REPORTED &
COMPLETED on 12-9-65

80 acre spacing - Lane prod from #2 Appleman

MISCELL DATA

GEOL _____ ELEV 3067 DFFTG _____ 3057 GR

SUPPT _____

CSG 7" @655 w/265 sx. 4" @4132 w/100 sx.SPUD DATE 4-28-65

DRLG COMP _____

FR by DATA 12-9-65COMP by " 12-16-65