

90014 /

7-287W Map No. K-78

OPER ROCK ISLAND OIL & REFG CO. -


Wichita, Ks.

WELL #1 APPLEMAN (Twin)

Wakefield Drlg.

Pollyana Pool (LKc Oil)

P 100 BOPD & 42% wtr, Lans 4132-35 (OH)



S-T-R 36-27S-35W

SPOT C SE SE

CO GRANT (Ks)

ELEV 3070 KB

(KB Sp1)

Hb 3997 - 927

Tor 4010 - 940

Lan 4085 - 1015

RTD 4133 - 1063

DDTD 4136 - 1066

DST #1 (Tor) 4018-4036, Op 2 hrs, R 15' Oil & 186' SOCMSW & 324' MSW, ISIP 1068#/60", FP's 77-230#, FSIP 1068#/60"

DST #2 (Tor) 4046-53, Op 2 hrs & 5", 2300' GIP, R 1120' CO & 160' MO & 20' MCOC filt wtr (Tor new zn), ISIP 1061#/45", FP's 150-510#, FSIP 1016#/45"

DST #3 (Lans) 4092-4105, Op 60", R 10' WCM, ISIP 992#/30", FP's 15-21W, FSIP 916#/30"

DST #4 (Lans) 4109-22, Op 2 hrs, R 1350' OCSW & 882' SOCSW, ISIP 1068#/45", FP's 429-1008#, FSIP 1063#/45", RTD 4133, Log, 4" @4132 w/100 sx.

CO & DD 4136 TD, .500A, \$ 1d, \$ 16 BOPH/

NT, POP, P 100 BOPD & 42% wtr OH, Lans 4132-36 - Gr NA
COMPLETED on 7-26-65

A₁

2600
1500
1100

Data Inc

C/SO EL Log - (Portion from 4076-4133)
Win 2670 + 394
Lans 4086 - 1016
A₁ 4126 - 1056

Oct. 1, 1965 - Lansing "B" Z plugged off due 80-acre spacing ruling. Cumm. Prod. 10,040 BO + 9,182 BW.

Perf (Tor) /4046-50

A/ Swb 12 BOPH (5% W).

State Pot. - Pmp 252 BOPD w/tr wtr 10/1/65

#2 Appleman producing on 80-acre unit S/2 SE/4.

L-S 307EOP
3062GL

MISCEL DATA	GEOI <u>Doug Marden</u>	ELEV <u>3057 GR</u>	SPUD DATE <u>4-28-65</u>
	FTG _____	<u>3067 DF</u>	DRLG COMP _____
	SUPPT _____	FR by DATA <u>5-4-65</u>	COMP by " <u>7-29-65</u>
	CSG <u>7" @655 w/265 sx.</u>	<u>4" @4132 w/100 sx.</u>	