

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


60381

Company - WILLIAM D. MOORER
Farm - Oehlert No. 1.

SEC. 7 T. 27 R. 4 W
S Ec SE

Total Depth. 4190'
Comm. 7-30-44 Comp. 8-23-44
Shot or Treated.
Contractor. H.M. Williams
Issued. 9-16-44

County. Sedgwick
KANSAS



CASING:
10" 215'

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

cellar	6
sand	60
shale & shells	191
lime & shale brks	312
shale & shells	700
lime & shale brks	765
lime & shale	895
shale & shells	1035
lime & shale	1255
shale & shells	1385
shale & lime	1630
shale & shells	1860
lime & shale brks	1925
lime & shale	2200
lime	2280
lime & shale	2445
lime	2505
lime & shale	2810
lime	2990
lime & shale	3130
lime	3179
lime sdy	3193
show oil 3179-93	
lime	3270
lime & shale	3380
shale & shells	3440
lime & shale	3540
shale & shells	3580
shale	3600
lime	3665
lime & chert	3730
shale & lime	3793
lime	3821
lime & shale	3842
lime	3896
shale & lime	3925
shale & shells	3960
shale	4018
Drill stem test @	4020
had 810' of wtr	
lime & sand	4049
lime & shale sdy	4074
sand & shale	4098
sand, lime & shale	4127
sand & lime	4152
lime	4190
Total Depth	
Top Miss lime	3600