

61447


Company - ANDERSON-PRICHARD OIL CORP.
Farm - Bartholomew No. 1.

SEC. 8
NWc NW

T. 27 R. 4 W

Total Depth. 4042
Comm. 12-1-44 Comp. 12-27-44
Shot or Treated.
Contractor. H. M. Williams
Issued. 2-17-45

County. Sedgwick
KANSAS



CASING:

10" 279'
5 1/2" 4035'

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

soil, sand keal or shale	60
sand & shale	150
shale & shells	400
shale	635
anhydrite & shale	850
shale & shells	1200
lime & shale	1300
shale & shells	1455
lime & shale	1580
shale & shells	1890
lime & shale	1925
shale & shells	2055
lime & shale	2520
lime	2565
lime & shale brks	2645
lime (lost mud 2690-94)	2745
lime & shale	2820
lime	3280
lime & shale	3310
shale & shells	3375
lime & shale	3445
lime	3480
lime & shale	3565
shale & shells	3600
shale	3625
lime (Miss)	3630
chert & lime	3668
chert	3683
chert & lime	3840
lime & shale	3900
shale & shells	3960
shale	4035
lime Viola (cored 4037-42)	4042
Total Depth (Rotary)	

TOPS:

Miss. lime 3625
Viola 4035

Drill stem test @ 3200 had
60' of salt wtr