

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Drille Strip
59814

Company - FRANK B. MURTA-T. JEFF ARCHER-
WM.D. MOORER-MARSHALL STROZIER
Farm - Branine No. 1.

SEC. 19 T. 27 R. 4 W
NE₃ NW

Total Depth. 4107'
Comm. 1-10-44 Comp. 2-1-44
Shot or Treated.
Contractor. Holm Drlg. Co.
Issued. 3-4-44

County. Sedgwick
KANSAS



CASING:
10" 191' Cem.
5 1/2" 4076' Cem.

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

shale & shells	200	Cable tool unit:
shale sdy	410	Corrected meas. on top
shale blue	590	of Viola Lime 4070
shale & shells	960	Simpson 4107
lime brkn	1020	Total Depth.
shale & shells	1145	
lime & shale	1160	
lime brkn	1210	3600' wtr from Viola Ls
lime gy hd	1235	3800' wtr from Simpson
lime	1285	
lime gy hd	1350	Tops:
shale & shells	1460	Iansing 2861
lime gy hd	1470	Miss. 3684
shale & shells	1730	Base Lima 3947
lime hd	1750	Sylvan 4045
shale & shells	1940	Viola (Corr) 4073
lime & shale	2040	Simpson 4096
shale & shells	2170	
lime	2190	Viola had a little oil
shale & shells	2240	& lots of wtr
lime gy hd	2286	2 1/2' cored
lime sdy sft	2300	3" rec. sft nice stain
lime gy hd	2350	& saturated, no wtr
lime	2360	
shale & shells	2730	
lime lgt brkn	2845	
shale & shells	2920	
lime lgt med	2980	
lime	2983	
lime gy hd	3080	
lime brkn	3145	
lime gy hd	3215	
lime	3265	
lime lgt hd	3267	
lime gy med	3330	
lime gy hd	3370	
lime lgt hd	3505	
lime	3545	
lime lgt	3575	
lime & shale	3630	
shale & shells	3686	
Miss. lime	3701	
lime & chert	3732	
lime & chert,hd	3760	
lime	3773	
lime & chert,hd	3830	
lime	3836	
lime lgt hd	3866	
lime	3904	
lime lgt hd	3945	
shale gy	3960	
lime & shale	3991	
shale gy med	4028	
shale & shells	4079	
lime sft	4083	
core 4080-83		