


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
508 East Murdock Wichita, Kansas

Company - CITIES SERVICE OIL CO.
Farm - De Pierro No. 2

SEC. 29 T. 27 R. 4W
NW NW SW
330' S. 330' E. of W $\frac{1}{4}$ Cor.
County. Sedgwick
KANSAS

Total Depth. 3759
Comm. 1-1-50 Comp. 1-19-50
Shot or Treated.
Contractor. R. W. Rine Drlg. Co. & Coffee Drlg. Co.
Issued. 6-23-51



CASING:
8 5/8" 214' cem. w/150 sx
5 1/2" 3738' cem. w/150 sx

Elevation. 1127 R.T.B.

Production. 155 BO NW/17 hrs

Figures Indicate Bottom of Formations.

red bed, shale & shells	215
lime & shale	690
lime	810
lime & shells	895
shale & shells	1075
lime	1105
shale & shells	1370
lime, sand, & shale	1835
lime	2490
broken lime	2600
shale	2715
lime	2800
broken lime	2885
lime	3060
sandy lime	3248
lime	3610
sandy lime	3669
shale & lime	3725
lime (dol.)	3759
Total Depth	

Tops:	
Brown Lime	2825
Base	2838
Lansing Lime	2848
Base	3327
Miss. Chert	3711

R.T.D. 3750'

Steel Line Measurement:
2860=2860
3666=3669
3717=3715

N.S.O. 2825
N.S.O. 2848
3711-38 N.S.O.
3738-41 S.O.
3741-45 N.S.O.
3745-59 S.O.

Best Pay 3738-59
First Free Oil in cuttings 3738'
First Free Oil in bailer 3756'
Gas bubbled through 3100' of wtr.
Bailed some free oil from T.D.

1-25-50 Flowed 155 bbls. oil, 0
wtr, 17 hrs. thru 3/4" choke, 600#
on casing before test; Dropped to
240# in 14 hrs. Increased to
400# at end of test.

Was not shot or az. upon completion.

All measurements taken from R.T.B.