

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
508 East Murdock Wichita, Kansas

Company - CITIES SERVICE OIL CO.
Farm - Durfee No. 5

SEC. 30 T. 27 R. 4W
NW SE SE
990' N, 990' W. of SE Cor.

Total Depth. 3760
Comm. 12-1-49 Comp. 1-2-50
Shot or Treated.
Contractor. Rine Drlg. Co. & Coffee Drlg. Co.
Issued. 7-7-51

County. Sedgwick
KANSAS



CASING:

Elevation. ~~1119~~ RTD

Production. 140 BO, 5 wtr 24/hrs

Figures Indicate Bottom of Formations.

red bed, shale & shells	210
shale & shells	695
lime & shells	785
lime & shale	830
lime	860
shale & shells	925
lime & shale	1335
lime	1460
lime & shale	1790
sand & lime	1970
lime & shale	2600
sandy lime	2730
shale & shells	2017
lime & shale	3270
lime	3365
lime & shale	3440
lime	3703
shale	3715
chert	3719
lime & chert	3756 RTD
lime	3760
Total Depth	

Tops:

Brown Lime	2857
Base	2866
Lansing Lime	2882
Base	3345
Miss. Chert	3715

Steel Line Measurement:

950=950
1124=1124
2868=2871
3652=3653
3735=3735

2857 N.S.O.
2882 N.S.O.
3715-40 N.S.O.
3740-44 S.O.
3744-52 Stain
3752-56 S.O.
3756-60 G.S.O.

Bailed sli. show free oil,
better than a good scum from
3756-60'

Best Pay in Chat 3752-60'

Gas in bailer only.

Az/ w/300 gals. used 46 bbls.
load oil.

All measurements taken from
R.T.B.