

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - HUBER & PABCO  
Farm - Berk

No. 1

SEC. 30 T. 27 R. 4W  
SW SE NE

Total Depth. 3748  
Comm. 1-13-49 Comp. 3-2-49  
Shot or Treated.  
Contractor. Pabco Drilling  
Issued. 4-16-49

County. Sedgwick  
KANSAS



CASING:

8 5/8" 195' w/200 sx  
5" 3725'

Elevation. ....

Production. 677 bbl. per day

Figures Indicate Bottom of Formations.

shale, shells	700
anhydrite	705
shale, lime	940
lime, shale	1155
lime	1305
shale, shells	1505
shale, salt	1810
shale, lime	2275
lime, shale	2470
shale, lime	2670
lime, shale	2780
shale, lime	2890
lime	3378
lime, shale	3645
shale, lime	3720
lime	3748
Total depth	

Tops:

Brown Lime	2844
Lansing	2877
Mississippi Lime	3710

Took Drill Stem Test 3714-50  
open 45 min. gas to surface /4 min  
Flowed oil cut mud /35 min &  
oil /40 min. Closed tool and  
flowed 45 min after closing Rec  
480' oil in drill pipe no free  
wtr. Bottom hole pressure 1100#  
Flow pressure 500# set 5" 3725.  
Loaded hole with 2700' wtr &  
drilled cement from 3688 to 3724 1/2  
leaving 26' open hole Ran swab  
twice and well flowed for 35 min.  
cleaning out Killed well and ran  
tubing Swabbed thru tubing to get well  
to flow Swabbed 8 hr and well flowed  
steady stream /3 hr into pits Shut  
in twodays and flowed 51.58 bbl oil  
1st hr; 28.3 bbl oil /2nd hr and 17.0  
bbl oil next 30 min. or 38.8 bbl  
per hr 2 1/2 hr Flowed 184 bbl oil 7 hr  
thru 1" choke plus .4% wtr Shut in  
csg. pressure 625# Casing pressure  
at end of test = 200#. Bottom hole  
Bomb-indicated capacity 677 bbl oil  
per day. Complete