

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 502 East Murdock, Wichita, Kansas

Company- KINGWICK OIL & GAS CO.
 Farm- Bartholomew No. 4

SEC. 30 T. 27 R. 4W
 CSW

Total Depth. 4141
 Comm. 9-30-51 Comp. 10-18-51
 Shot or Treated.
 Contractor. Group Explo. Co.
 Issued. 2-16-52

County Sedgwick
 KANSAS



CASING:

8 5/8" 160' cem. w/100 sx
 5 1/2" 3367' cem. w/50 sx

Elevation. 1127

Production. 2 BO & 90% wtr.

Figures indicate Bottom of Formations.

shale & shells	160
shale	215
shale & shells	675
shale& lime	890
lime broken	1050
lime & shale	1200
shale & lime	1320
shale & shells	1465
lime & shale	1565
shale & shells	1950
shale & lime	2840
shale	2865
lime	3505
lime & shale	3550
lime	3615
lime & shale	3660
shale	3712
miss. lime	3735
lime	3995
lime & shale	4050
shale	4075
shale & sand	4080
shale	4103
viola lime	4120
sand simpson	4141
Total Depth	

Scout Tops:	
Kansas City	2868
miss.	3712
Misener	4075
Simpson Dolo.	4116
Simpson Sand	4120

3 DST: in K.C. Lime
 1 DST: in miss. lime
 SS oil in Misener
 Testing showing of oil in
 K.C. lime at 3272-82 with
 pipe hung in hole and
 cemented at 3350 RTB.

3995
 147
 2568