

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas

Company - CITIES SERVICE OIL CO.
Farm - Lorenz No. 1

SEC. 31 T. 27 R. 4W
NW NE NE
330' S, 990' W of NE corner

Total Depth. 3754
Comm. 3-8-50 Comp. 3-28-50
Shot or Treated.
Contractor. R. W. Rine Drilg Co.
Issued. 9-9-50

County. Sedgwick
KANSAS



Elevation. 1415 RTB

Production. 539 bbls oil, 0 wtr.

CASING:
8 5/8" 203' cem w/150 sx.
5 1/2" 3721' cem w/150 sx.

Figures Indicate Bottom of Formations.

shale	245
sand	270
shale, shells	1100
lime, shale	2890
lime	3270
lime, shale	3704
lime, chert	3735
lime	3754
Total depth	

Tops:	
Brown lime	2849
Base Brown lime	2860
Lansing lime	2870
Base Lansing lime	3369
Miss. chert	370' ?

Rotary total depth 3745'

All measurements taken from R. T. B.

Steel line measure:

210 = 210

500 = 500

1550 = 1550

2750 = 2756

3660 = 3660

3746 = 3745

2849, N. S. O.

2870, N. S. O.

3704-23, NSO

3723-41, SSO

3741-45, FSO

3745-49, stain

3749-51, SSO

3751-54, stain

Bailed a scum of oil and bailing indicated gas at total depth.

Best pay 3741-51.

Not shot or acidized upon completion.