

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
508 East Murdock Wichita, Kansas

Company - W. C. MCBRIDE INC.
Farm - Dieffenbacher No. 2

SEC. 31 T. 27 R. 4W
SE SW SE

Total Depth. 3769

Comm. 3-25-51

Comp. 3-31-51

Shot or Treated.

Contractor. Tice Drlg. Co. & Jackson Drlg. Corp.

Issued. 7-7-51

County. Sedgwick

KANSAS



Elevation. 1410 D.F.

Production. 496 BO

CASING:

10 3/4" 209' cem.

7" 3758' cem.

Figures Indicate Bottom of Formations.

surface soil sand & shale	209
shale & shells	435
shale & salt	595
shale & lime	2245
shale	2260
shale & lime	2900
lime	3255
shale & lime	3724
chat	3768
T.D. Derrick Floor	3766'
chat	3769
Total Depth	

Tops:

Brown Lime	2862
Lansing K.C.	2903
Miss. Lime	3724

3-29-51 Acidized with 1000 gal. acid; Swabbed in, flowed 55 B.O. in 2 hrs. 3-3-51
4-11-51 Flow for 12 hrs. first 6 hrs. 159 B.O. Second 6 hrs. 134 B.O.
4-25-51 State Productivity 496 B.O. (flowing)
DST: 3768, packer 3758' open 30 min. fair steady blow. rec. 2400' gas, 120' gas & oil cut mud.
SIP, 15 min. 1375#.

Drillers log. Measurement from rotary bushing.