

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Merdock, Wichita, Kansas

Company- W. C. MCBRIDE, INC.
Farm- Dieffenbacher No. 13

SEC. 31 T. 27 R. 4W
NW SE SE
1648' fr WL 990' fr SL

Total Depth. 3776
Comm. 3-21-51 Comp. 4-24-51
Shot or Treated.
Contractor. Jackson Drlg. Corp. & O. H. Tice Drlg. Co.
Issued. 5-31-52

County Sedgwick
KANSAS



Elevation. 1402 DF

Production. IPP 496 BO & 3% wtr.

CASING:

10 3/4" 216' cem.
7" 3744' cem.

Figures Indicate Bottom of Formations.

clay & shale	40
sandy shale	65
shale & shells	590
shale & lime	2940
lime	3055
lime & shale	3085
lime	3240
lime & shale	3708
lime & chert	3776
Total Depth	

Tops:	
Brown Lime	2841
Lansing K.C.	2884
Miss.	3708
Dolomite	3754

4-12-51 Cleaned out to bottom
3763' Acidized w/1000 gal. acid.
Tosted 4 hrs. 15 gal. fluid scum
of oil. Perfejet with 39 shots
3741 to 3756. Acidized w/1000
gals. acid, tested 16.8 BO and
14.7 BW 24 hrs. small amount of
gas 4-22-51 Strata lift with
750 gal. Jol acid, 1500 gal.
acid Swab test 4-23-51
12 hrs. 50 BO 25 BW