

KANSAS WELL LOG BUREAU--- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY WESTGATE-GREENLAND OIL CO.

SEC. 31 T. 27 R. 4W


FARM Davis

NO. 8

LOC. SE SW SW

TOTAL DEPTH 3769  
 COMM. 9-29-50 COMP. 10-16-50  
 SHOT OR TREATED Acid 1000 gals.  
 CONTRACTOR Jackson Drlg Corp.  
 ISSUED 12-30-50

COUNTY Sedgwick  
 KANSAS



CASING

8 5/8" 198' cem w/135 sx.  
 5 1/2" 3756' cem w/ 75 sx.

ELEVATION 1421  
 Pot.  
 PRODUCTION 58 bbls

FIGURES INDICATE BOTTOM OF FORMATIONS

clay, sand	105
shale, shells	425
salt, shale	585
shale, lime shells	725
anhydrite	780
lime, shale	2905
lime, lime broken	2980
lime, shale	3032
lime	3162
lime, shale	3215
lime	3260
lime, shale	3655
lime	3727
Mississippi	3764
lime	3769
Total depth	

Tops:

Brown Lime	2860
Lansing	2900
Mississippi	3717
Dolomite	3756

ALL MEASUREMENTS FROM TOP OF DERRICK FLOOR.

Drill Stem Test: 3757-64.  
 Open 1 hr - recovered 30' oil & gas cut mud.

Acidized. Swabbing 35 bbls oil in 1 hour.