

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY CITIES SERVICE OIL COMPANY

SEC. 32 T. 27 R. 4W


FARM Guetschow NO. 1

LOC. NW NW NW
330' S, 330' E. of NW Corner

TOTAL DEPTH 3759
COMM. 5-26-50 COMP. 6-15-50

COUNTY Sedgwick
KANSAS

SHOT OR TREATED
CONTRACTOR R. W. Rine Dlr. Co.; Drill In: Pabco Drlg. Co.
ISSUED 2-3-51



CASING

8 5/8" 208' cem. w/150 sx
5 1/2" 3730' cem. w/150 sx

ELEVATION 1406' R.T.B.

PRODUCTION 142 bbls. fluid,
2% water/24 hrs.

FIGURES INDICATE BOTTOM OF FORMATIONS

All measurements taken from R.T.B.
(R.T.B. is 4.5' above grd.)

shale	520	Swabbed 13 1/2 bbls. oil, no wtr.
shale & shells	825	in 7 hrs. Az. w/1000 gals.,
lime	950	used 98 bbls. load oil.
lime & shale	1125	
sandy lime	1315	
lime	1330	
shale	1545	
lime & shale	1795	
shale	1920	
lime	1965	
lime & shale	2300	
lime	2465	
lime & shale	2980	
lime	3040	
lime & shale	3270	
lime	3310	
lime & shale	3430	
lime	3480	
lime & shale	3731	
chert	3746	
lime & chert	3759	
Total depth		

Tops:
Brown lime 2839
Base Brown lime 2849
Lansing 2872
Base Lansing 3343
Miss. chert 3709

Steel Line Measure:

2500=2500
2914=2921
3650=3653
3722=3724
3740=3740

Remarks:

Rotary Total depth 3758'
I. P. 142 bbls. fluid, 2% wtr.,
24 hrs. (Pump. unit) (Miss. Az.)
No show oil 2839; no show oil 2872,
3709-14, 3714-44; stain 3744-47;
no show oil 3747-51; fair show oil
3751-58 & 3758-59.
Best pay 3751-59; First Free oil 3751.
Bailed 3/4 bailer oil off bottom
through column of water. Gas came up
through column of water. Filled hole
w/water. Gas still came through fluid
but in lesser amount. Unloaded hole.