

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - KINGWICK OIL & GAS COMPANY  
Farm - Bartholomew No. 1

SEC. 30 T. 27 R. 4W  
SEc SW

Total Depth. 3737'  
Comm. 5-22-46  
Shot or Treated.

Comp. ~~6-8-46~~ 7-22-46

County. Sedgwick  
KANSAS

Contractor. Foster & Abplanalp  
Issued. 3-8-47



Elevation. \_\_\_\_\_

Production. 5,000,000 Gas

CASING:

8-5/8" 153' Cem.  
5-1/2" 3695' Cem.

Figures Indicate Bottom of Formations.

shale, shells & gravel	0-85
sand, shale & gravel	460
shale & lime	825
shale & lime brkn	865
salt & shale	935
salt, shale & lime brkn	1068
lime	1235
shale & lime	2153
shale & lime strks	2220
shale & lime	2857
shale & lime strks	2917
shale & lime	3025
lime	3059
shale & lime	3171
lime	3209
shale & lime	3223
lime	3284
shale & lime	3441
shale & lime brkn	3534
shale	3561
shale & lime	3690
lime	3697
lime & chert	3737
Total Depth	

Cor. D.D.  
2/20/47

Drilling in record. June 20, 23, 1946:

- First show of gas @ 3707
- 15 M gas @ 3710
- 25 M gas @ 3712 1/2
- 33 M gas @ 3714
- 55 M gas @ 3718
- 160' muddy water @ 3718
- 73 M gas @ 3725 - water exhausting
- 76 M gas @ 3725 \* show of oil 3726 to 3728
- 85 M gas @ 3727 hole bailed dry, oil tested
- 85 M gas @ 3732 1/2 24 hrs., bailed 2 1/2 bbls.

June 24th bailed hole dry, 115 M, R.P. 1040 in 14 hrs.  
June 25th R.P. 1190# in 21 hrs.  
July 16th to July 22nd.  
Walker Drig. Co. - Hutchinson, Ks.

Well drilled to 3737 by Walker. T. D. 3737'  
July 22 acidized w/500 gallons.  
July 22-5,000,000 Gas-R.P. 1390  
July good spray of oil. No wtr after blowing 6 hrs.  
July Well shut in for market connections.

Tops:

Lansing K. C. 2875  
Mississippian 3691