



DEC 30 1971

CONTRACTOR'S WELL LOG

OPERATOR:	Kansas Petroleum, Incorporated
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAM:E	<u>NORDLING #1</u>
LOCATION:	C NE/4 Sec. <u>4-27S-40W</u> Stanton County, Kansas

GEOLOGIST:	
SPUD DATE:	December 19, 1970
COMPLETION DATE:	December 23, 1970 <i>Shut in Gas Well</i>

0	165	Clay - Rock & Sand
165	475	Shale
475	575	Rock
575	1120	Shale
1120	1140	Shale and Shells
1140	1430	Salt
1430	1800	Shale
1800	1813	Anhydrite
1813	2195	Shale and Lime
2195	2570	Lime and Shale
	2570	Rotary Total Depth

Set 14 joints of 8-5/8" surface casing at 564' w/300 sx. 2% gel. Cement circulated. Plug was down at 7:00 a.m. 12-19-70. Ran 5-1/2" casing and set @2567' w/350 sx. cement. Plug was down at 1:00 a.m. 12-23-70.

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Jerry A. Langrehr, President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the NORDLING #1, C NE/4 Sec. 4-27S-40W, Stanton County, Kansas.

ABERCROMBIE DRILLING, INC.

By: *Jerry A. Langrehr*
Jerry A. Langrehr
President

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 28th day of December, 1970.

Sue J. McCoy
Sue J. McCoy, Notary Public

My Commission Expires: