

KANSAS GEOLOGICAL SOCIETY
508 East Murdock
Wichita, Kansas

4-27S-6W

SEP 6 1969

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

KING #3
C SE SW Section 4-27S-6W
Kingman County, Kansas

Commenced: May 23, 1969
Completed: June 7, 1969

OPERATOR - Thunderbird Drilling, Inc.

oil

DEPTH		FORMATION	REMARKS
From	To		
0	265	Sand and red bed	
265	970	Shale and red bed	Ran 7 joints of 10-3/4" casing, set @ 265' w/225 sacks cement.
970	1300	Shale and shells	
1300	3080	Lime and shale	
3080	4025	Lime	
4025	4142	Shale	
4142	4183	Lime	
4183	4273	Lime and shale	
4273	4450	Lime	
4450	TD		Ran 113 joints of 7" casing, set @ 4247' w/135 sacks cement. DV tool @ 3450' cemented w/165 sacks thru DV tool.

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the C SE SW Section 4-27S-6W, Kingman County, Kansas to the best of my knowledge and belief.

E. E. Hall
E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 10 day of June, 1969, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires Feb. 1, 1972.

Barbara J. Layton
Barbara J. Layton, Notary Public