


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- W.J. COPPINGER ET AL
Farm- Robinson No. 1

SEC. 32 T. 27 R. 6W
SE SE SE

Total Depth. 4405'
Comm. 8-19-57 Comp. 9-5-57
Shot or Treated.
Contractor. D & M Drlg. Co.
Issued. 12-28-57

County Kingman
KANSAS



CASING:
8" 254'

Elevation. 1528' RB

Production. Dry

Figures indicate Bottom of Formations.

Sample Description.

limestone; cream, finely crystalline to chalky, poor spotted pinpoint porosity, no stain, no odor, no fluorescence. 2869-2874
Sandstone; white, light gry, fine grain, calcareous, micaceous, shaly, fair porosity, no show. 2900-3089
Limestone; cream oolitic, good oolitic porosity, no shows. 3188-3194
Limestone; buff, finely crystalline, traces of pinpoint porosity, no shows 3282-3286
Limestone; cream, buff, fossiliferous, chalky, slightly cherty, fair pinpoint porosity, no shows. 3401-3414
Limestone; buff, gray, good oolitic porosity, no shows. 3490-3494
Limestone; cream, gray, chalky, good oolitic porosity, no shows. 3536-3550
Chert; white to cream, tripolitic, spongy, good pinpoint and vugular porosity, trace of free oil, scattered dark staining, good odor. 3863-3906
Sandstone; white to buff, very fine grained, calcareous, silty, poor to fair porosity, slightly pyritic, no shows. 4232-4242
Dolomite; light gray, medium to coarsely crystalline, slightly pyritic, spotted good porosity, light stain, fair show of free oil, faint odor. 4252-4257
Sandstone; white to buff, medium grain, sub-rounded, calcareous in lower part, fair porosity, no shows. 4271-4312
Dolomite; tan to gry., medium crystalline to dense, slightly shaly and cherty, poor to fair vugular porosity, no shows. 4380-4405
Total Depth 4405

myddy oil, 60' slightly muddy oil, slightly wtr. cut, 60' salt wtr.; ISIP 1525#; IFP 50#; FFP 265#; BHP 1525# s.i. 20 min.

Ran Halliburton log.

TOPS:	Sample	Elec.
Heebner	2855	2852
Toronto	2868	2864
Douglas sand	2900	2901
Brown lime	3112	3110
Lansing	3129	3118
B/Kansas City	3596	3594
Mississippian	3863	3860
Kinderhook	4152	4152
Viola	4252	4252
Simpson sand	4269	4271
Arbuckle	4374	4380
Total Depth	4405	4402

DST #1; 3865-3890; open 1 hr; rec. 120' slightly OCM, 320' salt wtr; ISIP 1485#; IFP 50#; FFP 205#; BHP 1260# s.i. 20 min.

DST #2; 4245-4257; open 1 hr.; rec. 50'