


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- DRILLERS PRODUCTION CO., INC.
Farm- Orme No. 1

SEC. 34 T. 27 R. 6W
SW SW NW

Total Depth. 4423'
Comm. 1-3-58 Comp. 1-20-58
Shot or Treated.
Contractor. Walters Drilling Co.
Issued. 2-22-58

County Kingman
KANSAS



CASING:
8 5/8" 258' cem w/200 sx

Elevation. 1493'DF

Production. Dry

Figures indicate Bottom of Formations.

surface	258
shale & red bed	875
salt & shale	1135
shale & lime	3161
lime	3631
lime & shale	3705
lime	3850
lime & shale	3853
lime	3874
chert	3933
lime, chert & shale	3978
lime & shale	4011
lime	4107
chert & lime	4144
lime	4196
shale	4240
lime & shale	4287
sand, shale & lime	4325
lime & shale	4423
Total Depth	

TOPS:	
Heehner Shale	2816
Toronto Lime	2830
Douglas Shale	2849
Douglas Sand	2871
Brown-Lansing Lime	3076
Base Kansas City	3563
Mississippi	3852
Mississippi Chert	3859
Mississippi Lime	3871
Kinderhook	4158
Maquoketa Dolomite	4253
Viola	4263
Simpson Sand	4285
Arbuckle	4387

DST - 3892-3928, open 1 hour, weak blow,
Rec. 250' watery mud, IF-FFP
43-147, ICIP/30" 1524, FCIP/30"
1436.