

**RUPP-FERGUSON OIL CO.**

522 UNION CENTER      TELEPHONE 341-4611  
WICHITA, KANSAS

WELL COMPLETION DATA

Date 7-13-60

NAME Freemyer No. 1 Pool Wildcat County Kingman

Legal Description C SW/4 SE/4 Sec. 20 Twp. 27 Rge 6W

660' From the South Line 660' From the West Line of the SE/4 Qtr.

Drilled by Rupp-Ferguson Oil Co. Operated by Same

Cable Tools by Dover Drlg. Co. Rotary Bushing T. D. 4212

All Measurements Rotary Bushing and Rotary Bushing is 6.5 Feet above the top of the Braden

Head on the Surface Casing.—R. B. Elevation 1545 Ground Level Elevation 1540

Surface CSG. Set at 253 Feet. Make \_\_\_\_\_ Grade Used Weight 28

RGE. 1 Set With \_\_\_\_\_ Sacks of Cement by Globe Cem. Co.

Type of Cement Portland Size of CSG. 8 5/8"

Oil String Set at 3893 Feet. Make Sml Grade J-55 Weight 14

RGE. 2 Set with 100 Sacks of Cement by Globe Cem. Co.

Type of Cement Pozmix Size of CSG. 5 1/2

Type Centralizer Baker Hinge Shoe Baker Formation Packer Float Baker Flex-Flow

Centers of Centralizer Located at R. B. 3728

Top of Float at 3860 Length of Shoe Joint 33.00 No. Plugs 2

Kind of Plugs Rubber Feet of Open Hole by Rotary 330'

Date Spudder Moved In 7-13-60 Total Spudder Hours 68

Date Spudder Finished 7-17-60 Total Swab Rubbers used \_\_\_\_\_

Completion From 3828 To 34 In The Mississippi

Brief Sample Desc., Each Run of Bit, Along W/ Test, Perforations, and Well Reaction:

REMARKS: 7-13-60 Swab hole dry Perf. by Lane Wells 3828-34 Jets 4 shots per ft.

Fair blow of gas. 300,000

Run 2" tbg Acidize w/500 gal. MCA by Dowell swab back load.

Acid or Fracture, Maximum Pressure \_\_\_\_\_ Minimum Pressure \_\_\_\_\_ Acid Feeding Press. \_\_\_\_\_

REMARKS: Testing well - making after 12 hrs. venting 930,000 Csg. 980# Tbg 865#

Gas is somewhat wet.

Dead wt. Csg. 1315# Tbg 1220# 7-30-60

Well testing 2 1/2 to 3 million well.

Tests: \_\_\_\_\_

Please fill out completely any additional information. Completion in other zones should be noted on the back in their proper order as above. Fill in the wells and their number on the following Plat:

PERSON COMPLETING THIS WELL:

*Top*

(SGD) A.F. Oberle

SE/4


205

6	5	4	3	2	1
7	8	9	10	11	12
18	17	16	15	14	13
19	20	21	22	23	24
30	29	28	27	26	25
31	32	33	34	35	36

T \_\_\_\_\_  
R 35W  
Cty \_\_\_\_\_