


Company - PHILLIPS PETRO.CO.
Farm - Kuhns No. 1.

SEC. 3 T. 27 R. 7 W
S Wc NW

Total Depth. 4368'
Comm. 7-7-44 Comp. 8-9-44
Shot or Treated.
Contractor.
Issued. 10-21-44

County. Kingman
KANSAS



CASING:
8 5/8" 391'

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

sand & shale	30
red rock	70
shale & sand	160
sand	370
shale & shells	390
shale	410
shale & shells	720
salt	840
shale & lime	960
shale & shells	1030
lime brkn	1135
lime	1350
lime brkn	1430
lime	1846
lime & shale	2410
lime brkn	2498
lime & shale	2672
lime	2959
lime & shale	3004
lime brkn & shale sdy	3124
shale	3160
lime & shale	3175
lime	3424
lime hd	3445
cherty lime	3472
lime	3506
lime & shale	3544
lime	3623
shale	3658
lime & shale	3701
shale	3856
chat	3873
lime	3898
chat	3941
shale	3981
lime	3991
lime & shale	4030
lime	4050
shale	4178
shale strks	4210
lime	4232
sand & shale	4265
sand, shale & lime	4303
shale	4326
shale sdy	4340
lime	4368

Total Depth Corr.

Tops:

Lansing KC	3179 Corr. Dry
Miss	3854 DF
Show gas, strks Oil stain	
Kinderhook	4026
Klyn Viola	4198
Simpson	4231
Arbuckle	4338

4026
2854
192