


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- TENNESSEE GAS TRANSMISSION CO.  
Farm- A. W. Wallace No. 1

SEC. 20 T. 27 R. 7W  
SE SE SE

Total Depth. 4395'  
Comm. 4-22-57 Comp. 5-11-57  
Shot or Treated.  
Contractor. Virginia Drlg. Co.  
Issued. 5-2-59

County Kingman  
KANSAS



CASING:

8 5/8" 244'

Elevation. 1607' KB

Production. Dry

Figures Indicate Bottom of Formations.

surface clay - sand -  
red bed & shale 210  
red bed & shells 595  
Anhydrite 605  
grey shale & shells 715  
shale-shells 920  
salt 955  
shale-shells 1040  
gyp 1150  
gyp-shale 1255  
shale-lime 1290  
lime broken 1355  
shale-lime 1640  
lime Ft. Riley 1740  
lime-shells-shale 1845  
lime-shale 2330  
lime 2460  
shale-lime 2515  
lime 2610  
lime-shale 2665  
shale-sandy 2710  
lime 2835  
lime-shale 2935  
lime 3070  
shale-sandy lime 3198  
lime-shale 3275  
lime 3440  
lime-chert 3470  
lime 3516  
lime-shale 3583  
lime 3700  
shale-lime-chert 3740  
lime 3787  
lime-shale 3900  
lime-chert 3915  
shale-lime 3945  
Mississippi lime 3956  
Mississippi chat 4039  
lime-shale 4055  
lime-chert-shale 4082  
lime-shale 4258  
lime 4263  
Viola 4278  
lime-shale 4282  
sand 4318  
sand-shale 4348  
shale-lime 4390  
lime 4395  
Total Depth

DST #1 3340-84', op 1 hr, rec. 1140' SW,  
BHP 1395#-1330.  
DST #2 3946-56' op 2 hrs, rec. 60' SGCDM  
BHP 1430#.  
DST #3 3956-66', op 1 hr, 190' muddy wtr. scum oil,  
BHP 1475-1370.  
DST #4 4259-63', op 1 hr, 370' GCMSW - BHP 1290#.  
DST #5 4285-4318', op 1 hr, 100' muddy SW,  
BHP 1455-1305.

TOPS:

Heebner 3034  
Brown Lime 3231  
Lansing 3246  
Mississippi 3947  
Kinderhook 4110  
Viola 4255  
Simpson 4275  
Arbuckle 4370