

Gypsy, Allison & Fitzwilliams,
Kingman County, Kansas.
SE NW NW.

Sec. 25; T. 27S; R. 7W.
Wilkinson #1.
By A. S. Price.

3895 to 3900....Shale, various-colored. Trace chert, white, weathered.
3920 to 3930....Shale, various-colored. Limestone, grey. Trace chert.
3930 to 4135....Mississippi chert. Limestone. TOP MISSISSIPPI LIME 3930'.
4135 to 4160....Limestone, brownish-grey, finely-crystalline.
4160 to 4165....Shale, dark-grey, granular, dolomitic.
4165 to 4275....Shale, dark, finely-textured. TOP KINDERHOOK*CHATTANOOGA SHALE 4160'
4275 to 4283....Dolomite, brown and white, crystalline, porous.
(looks like dolomitized Viola). TOP VIOLA 4275'.
4283 to 4286....Dolomite, light brownish-grey, crystalline.
4286 to 4292....Dolomite as above, sandy.

TOP WILKINSON ABOUT 4292'.