

2850J

Kingsman County Oil and Gas Co.
NE NW,
Kingsman County, Kansas.

S. 21; T. 27S; R. 7W,
C. Bayle,
By: A. S. Price.

CABLE TOOL SAMPLES:

- 680 to 690.... Sand, medium, coarse, rounded; shale, gray and red.
- 690 to 700.... Sand, medium, coarse, rounded; shale, various colored.
- 700 to 710.... Shale, gray and red with trace anhydrite.
- 710 to 720.... Shale, gray and anhydrite with trace salt.
- 720 to 730.... Shale, gray and anhydrite; salt.
- 730 to 740.... Shale, gray; anhydrite and salt.
- 740 to 780.... Shale, gray with trace anhydrite and salt.

TOP OF SALT 780.

- 780 to 880.... Salt; shale, gray.
- 880 to 885.... Missing.
- 885 to 900.... Salt; shale, gray.
- 900 to 1015.... Salt; shale, gray.
- 1015 to 1025.... Anhydrite.
- 1025 to 1050.... Anhydrite, salt and shale, gray.
- 1050 to 1100.... Salt.

BASE OF SALT 1100.

- 1100 to 1110.... Anhydrite.
- 1110 to 1120.... Missing.
- 1120 to 1150.... Anhydrite.
- 1150 to 1160.... Anhydrite and gray shale, 60%.
- 1160 to 1170.... Shale, gray; anhydrite; dolomite, dull brown, dense.
- 1170 to 1180.... Shale, gray; anhydrite, and dolomite.
- 1180 to 1190.... Dolomite, anhydrite, shale, gray.
- 1190 to 1200.... Anhydrite, shale, gray and dolomite.
- 1200 to 1250.... Anhydrite.
- 1250 to 1260.... Dolomite, brown, shaley and anhydrite.
- 1260 to 1270.... Anhydrite, limsy, impure.
- 1270 to 1280.... Anhydrite, limsy, impure.

TOP OF CHASE 1285 (?).

- 280 to 1290.... Shale, gray.
- 1290 to 1300.... Chert, dolomite and shale.
- 1300 to 1310.... Shale, gray, dolomitic.
- 1310 to 1320.... Shale, gray, dolomitic.
- 1320 to 1326.... Limestone, shaley, cherty.
- 1326 to 1337.... Limestone, gray, light brown, shaley.
- 1337 to 1345.... Shale, gray, calcareous, dolomitic.
- 1345 to 1350.... Shale, green and red, calcareous.

DRY. MISSED GAS SAND.