


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- AYLWARD DRLG. & AURORA GASOLINE CO.
Farm- Layman No. 1

SEC. 8 T. 27 R. 8W
NE NE NE

Total Depth. 4491'
Comm. 10-22-55 Comp. 11-7-55
Shot or Treated.
Contractor. Aylward Drlg. Co.
Issued. 4-20-57

County Kingman
KANSAS



CASING:
8 5/8" 160' w/135 sx cem.

Elevation. 1644' DF

Production. Dry

Figures indicate Bottom of Formations.

sand	85
red rock-lime	105
red rock-lime stks	160
red rock-shale	375
shale-red rock	460
Anhydrite	470
shale-lime	870
salt	910
shale-lime	1220
shale	1235
Ft. Riley lime	1380
lime	1560
shale-lime	1825
shale	2020
lime-shale	2400
shale-shells	2700
shale-lime strks	2870
shale-lime	3525
lime	3980
lime-chert	4002
Mississippi chat	4073
lime-shale	4102
shale	4290
lime-shale	4304
lime-cherty	4309
lime	4358
sand-shale	4490 RTD
sand-shale	4491
Total Depth	

TOPS:

Heebner	3144
Toronto	3154
B/Oread (scout)	3172
Douglas sand	3185
Brown lime	3342
Lansing Kansas City	3358
Mississippi	3988
Kinderhook	4100
Viola	4302
Simpson	4464
Arbuckle	4491

DST #1 - 3989-4002- open 1 hr.
Rec. 100' HGCM & 270' salt wtr.
BHP 1150#, 30 min.

DST #2 - 4298-4304- open 1 hr.
Rec. 160' gas, 85' oil & GCM,
BHP 280# 30 min.

DST #3 - 4303-09 - open 1 hr.,
Rec. 15' mud BHP 0#.

DST #4 - 4463-90 - open 1 hr.,
945' salt wtr, BHP 1500# 15
min.