

156
✓

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
211 NORTH BROADWAY
WICHITA, KANSAS

WELL PLUGGING APPLICATION FORM

File One Copy

Lease Owner Shawver-Armour, Inc. Address 817 Central Building
(Applicant)
Lease (Farm Name) Hay Well No. 3
Well Location SW NE NW Sec. 36 Twp. 28 Rge. (E) - (W) 1
County Sedgwick Field Name (if any) Gladys
Total Depth 3300 Oil Gas Dry Hole x
Was well log filed with application? yes If not, explain:

Date and hour plugging is desired to begin 4 a.m. February 17, 1956
Plugging of the well will be done in accordance with the Rules and Regulations
of the State Corporation Commission.

Name of the person on the lease in charge of well for owner

Paul Horsch Address Riverdale, Kansas

Plugging Contractor Shawver-Armour, Inc.

Plugging Contractor's License No.

Address 817 Central Building, Wichita, Kansas


Invoice covering assessment for plugging this well should be sent to

Shawver-Armour, Inc Address 817 Central Building

and payment will be guaranteed by applicant.

James Armour
Applicant or Acting Agent James Armour

Date 2-22-56



CONSERVATION DIVISION
Wichita, Kansas



STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
211 NORTH BROADWAY
WICHITA, KANSAS

February 21, 1956

Well No.	3
Lease	Hay
Description	SW NE 1/4 36-28-1W
County	Sedgwick
File No.	40-21

Shawver & Armour, Inc.
817 Central Building
Wichita, Kansas

Gentlemen:

This letter is your authority to plug the above subject well, in accordance with the Rules and Regulations of the State Corporation Commission. When you are ready to plug this well, please contact our District Plugging Supervisor, Mr. Ruel Durkee, Box 597, McPherson, Kansas.

STATE CORPORATION COMMISSION
CONSERVATION DIVISION

By S. S. Greider
S. S. Greider
WELL PLUGGING SUPERVISOR

cc:
District Plugging Supervisor



STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
211 NORTH BROADWAY
WICHITA, KANSAS

T. A. Morgan, Director
State Corporation Commission
211 North Broadway
Wichita, Kansas

Dear Sir:

I have this date 2-17, 1956, given verbal
permission to the following plugging operation:

OPERATOR Shannon & Armon Inc
ADDRESS Wichita Kans
FARM NAME Hay WELL NO. 3
DESCRIPTION SW-1/4-21W Sec. 36 Twp. 28 Rge. 1W
COUNTY Sedgewick
TOTAL DEPTH 3267 OIL GAS DRY HOLE ✓
PLUGGING FEE TO BE PAID BY
ADDRESS

Very truly yours,

Paul D. Burke
District Agent

RECEIVED 2-20-56
STATE CORPORATION COMMISSION
Date
FEB 21 1956
CONSERVATION DIVISION
Wichita, Kansas

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. ✓

LOCATION SW-NE-SW

SEC. 31 TWP. 28 RGE. 1W

Dry Hole ✓ Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 3 Lease 244 817 Central Bldg.

Operator Shannon & Gorman Inc. Address Wichita, Kansas

Field _____ County Sedgewick

Total Depth 3247 Feet.

Plugging Contractor Company to be

Plugging Contractor's License No. _____

Address _____

(Describe briefly the manner in which the well was plugged)

Grouted pits and circulated. Hole made
solid at approx 185, 15 sec concrete
Three 6 joints drill pipe. Mud to 30,
bridged, 5 sec concrete at top.

Paul D. Dyer
District Conservation Agent

Date 2-20-56

PLUGGING
FILE SEC 36 T 28 R 1W
BOOK PAGE 40 LINE 31

RECEIVED
FEB 21 1956
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

Sedgwick County. Sec. 36 Twp. 28 Rge. 1 (E) (W)
Location as "NE/CNW%SW%" or footage from lines SW NE NW
Lease Owner Shawver-Armour, Inc.
Lease Name Hay Well No. 3
Office Address
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 2-17-56 19
Application for plugging filed 2-17-56 19
Application for plugging approved 2-17-56 19
Plugging commenced 2-17-56 19
Plugging completed 2-17-56 19
Reason for abandonment of well or producing formation Dry Hole
If a producing well is abandoned, date of last production none 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

NORTH

Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation Mississippian Depth to top 3214 Bottom 3300 Total Depth of Well 3300 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface	water	0	194	8-5/8	194	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

3300 - 180 Fill w/ heavy mud
180 Good permanent plug and 15 sx cement thru drill pipe
30' Fill w/ heavy mud. Then set #2 plug - good permanent plug
and 10 sax cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Shawver-Armour, Inc.
Address 817 Central Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
James Armour


(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James Armour James Armour
817 Central Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 22 day of February, 19 56

My commission expires Dec. 29, 1959

Marjorie Hall
Notary Public.



FEB 23 1956
CONSERVATION DIVISION
Wichita, Kansas

DRILLING LOG

COMPANY: Shawver-Armour, Inc.
CONTRACTOR: Shawver-Armour, Inc.

Location: SW NE NW 36-26-1N
Sedgwick

FARM NAME: MAY #3

Elevation: 1301.88

COMMENCED: February 9, 1956
COMPLETE: February 17, 1956

CASING RECORD
8-5/8 198' 175 sq. cm.

FORMATION	FROM	TO	
Surface Clay & Sand		60	
Sand & Gravel		100	
Clay, Shale w/shells		167	
Anhydrite		195	
Anhydrite w/shale & shells		275	
Shale & Lime		460	TOPS
Lime & Shale		615	
Shale w/lime shells		960	Kansas City 2714
Shale & Lime streaks		1365	Mississippi Chert 3210
Shale & Shells		1580	Mississippi Dolo. 3256
Lime & Shale		2105	RTD 3300
Shale		2381	
Stalactite sand & Shale		2501	
Lime & Shale		2683	
Shale & Lime Shells		2715	
Lime		2780	
Lime		2900	
Lime w/shale		3095	
Shale w/lime		3115	
Lime & Shale		3215	
Lime		3300	

STATE OF KANSAS)
SEDOWICK COUNTY)

I, James Armour, do hereby certify that the above is a true and correct copy of the log on the above captioned well, as shown on the daily drilling reports.

SHAWVER-ARMOUR, INC.

By James Armour
James Armour, Sec. Treas.

Subscribed and sworn to before me this 22 day of February 1956.

Marjorie Hall
Notary Public - Marjorie Hall

My commission expires December 29, 1959

