

36-28-10W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- FRED & PHILLIPS ANSCHUTZ
Farm- Adelhardt No. 1

SEC. 36 T. 28 R. 10W
C SW NE

Total Depth. 4672'
Comm. 11-27-63 Comp. 12-10-63
Shot or Treated.
Contractor. Terrel Drilling & Producing
Issued. 2-8-64

County Kingman
KANSAS



Elevation. 1731' KB

CASING:

8 5/8" 230' cem w/175 sx.

Production. Dry

Figures Indicate Bottom of Formations.

sand & shale	230
redbed	482
shale & shells	1090
shale & lime	1575
shale & shell	1718
lime & shale	3703
lime	3818
lime & shale	3874
lime	3995
lime & shale	4047
lime	4190
lime & chert	4247
lime	4317
lime & chert	4370
lime & shale	4413
lime	4479
lime & shale	4512
lime	4570
sand	4576
sand & lime	4608
sand, lime & shale	4670 RTD
sand, lime & shale ?	4672
Total Depth	

TOPS:	<u>SAMPLE</u>	<u>ELECTRIC</u>
Heebner	3445	3438
Toronto		3463
Douglas	3501	3502
Lansing	3683	3641
Base Kansas City		4018
Mississippi Chert	4180	4178
Kinderhook	4276	4276
Viola	4474	4473
Simpson	4544	4542
Arbuckle	4642	4642

Electra, Inc., Gamma Ray-Neutron-Accurlog,
base surface to total Depth

DST #1 4179-90' Op 1 hr. Opened w/good
blow-continued throughout. Rec. 210' oil
cut & slightly gas cut mud, 660' slightly
oil cut wtr. IBHP 1465/30", FBHP 1373/30".
IFP 54#, FFP 401#.