


90213 L-S 3095 DF.

A-7-141

3097 3072 KB
3086 3061 GL

MAP NO. 78
STATE Kansas COUNTY Grant SEC. 13 Twp 28 S Rge 36 W
OPERATOR Columbian Fuel Corporation - Liberal, Kansoc. C SE NW
WELL NO. 2 FARM NAME C. R. Davatz "B" FT. FROM _____ LINE _____
COL Geol Wildcat (Hugoton-Panoma) (PD 5600) FT. FROM _____ LINE _____
FR. 5-4-61 SPUD 5-3-61 COMP. 7-15-61
CONT./GEOL. R. W. Rine rig # 2

COMPLETION RECORD			
NAME PRODUCING INTERVAL	FROM - TO	PERF. W/HOLES	TREATMENT RECORD
a Council Grove	2846-2908	104	2500A-F/60X60
b Morrow	5231-32	Abra	F/20X20
c			
d			



d I. P. OIL/DIST. _____ WTR. AOF GAS 2,000 M.C.F.P.D. _____ CHK. _____ HRS. _____
b " P/144 BOFD " " " " P " 24
c " " " " " " " "
d

D & A ()

SIP#	FI TP #	FI CP#	SIBHP
350 (a)			
GOR.	GR. <u>38° (b)</u>	PBTD <u>5247</u>	TD <u>5850</u>
CASING - CEMENT RECORD			
SIZE	DEPTH	W/SAX.	DEPTH
<u>13-3/8"</u>	<u>555</u>	<u>450</u>	<u>9-5/8"</u>
<u>5 1/2"</u>	<u>5281</u>	<u>850</u>	<u>3029</u>
			<u>400</u>

OPERATOR Columbian Fuel WELL NO. 2 C. R. Davatz "B" ELEV. 3072 KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
Winfield	2626	+ 446	Heebner	3978	
Council Grove	2856		Toronto	4000	
Lansing	4072		Lansing	4080	
Marmaton	4685		Marmaton	4684	
Morrow	5220		Morrow	5210	
Chester	5460		Morrow Sand	5216-38	
Ste. Genevieve	5525		Chester	5412	
			Ste. Genevieve	5580	
			St. Louis	5636	

Spud 5-3-61. 13-3/8" @ 555 w/450 sx. Mud logger on location, had SG in Council Grove. 9-5/8" @ 3029 w/400 sx.

- DST # 1 (Lans?) 4514-26, op 2 hrs, rec 1230' GCSW, FP 63-443, SIP 1161/30 mins.
- DST # 2 (Morr) 5216-37, op 2 hrs, GTS 65 mins, ga 12 MCF, rec 430' oil + 150' HO&GCM + 120' MCO (gty 38°), ISIP 1566/30 mins, FP 111-200, FSIP 1497/30 mins.
- DST # 3 (Morr) 5241-84, op 1 hr, rec 10' VSGCM, FP 42-42, SIP 42/30 mins.
- DST # 4 (Morr) 5444-59, op 2 hrs, rec 2810' SGCSW, FP 548-1375, SIP 418/30 mins.

RTD 5850, logs (Sj). 5 1/2" @ 5281 w/850 sx. MICT. CO 5247.
 P/Abrosajet @ 5231-32. frac 20,000 gel oil x 20,000 sd. swb
 755 BL + 60 NO/12 hrs, GOR 280. set BP @ 2930.
 P 28/2894-2908, 500 MA. swb ld, g 58 MCF + 69 GL.
 P 36/2872-90, 24/2856-68, 16/2846-54. trt 2846-90 w/2000 MA
 swb 61 BL w/33 MCF. swb 24 BL w/56 MCF. frac 60,000 Ac
 X 60,000 sd. had fish, rec. pld BP @ 2930. set 2 3/8"
 tbg @ 5220. fr 2846-2908 20 min BD 1329 MCF. AOF 1,800 MCF
 ltr g 1704 MCF w/mist wtr, FCP 25. POP.

IP P/6 BOPH/24 hrs (144 BOPD), no wtr, gty 38° from Morrow
 5231-32.

IP AOF 2,000 MCF, SIP 350 from Council Grove 2846-2908.
 DUAL COMPLETION.

LIBERAL TOPS

3097 KB

Correct all Datum 25' UP.

3072 GL

Win 2622 + 450

Heebner 3978 (-906)

Toronto 4000 (-928)

Lansing 4080 (-1008)

Marmaton 4684 (-1612)

Morrow 5210 (-2138)

"S-1" 5216 (-2144) 6/22 x 86 sample -14480
 sd or lm? 5330 (-2258) 10/38 brkn

Chester ? 5412 (-2340)

St. Gen 5580 (-2508)

St. Louis 5636 (-2564)

TD 5850

? Ch sd 5442 - 2370 24/24 2810' x W 380

C Grove 2856 + 241 239

Kansas Sample Log Tops

St. Riley 2675

Flanner 2770

Wierford 2830

new 3022

Howard Top 3487

Raising ? 4034

Morrow 5210

Muss 5330

False St. Louis 5637-58

3095
 2856
 239