

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

36-28-14W

Company. PHILLIPS PETROLEUM CO.
Farm. Pratt "A" No. 1

SEC. 36 T. 28 R. 14W
NW NW NE

Total Depth. 4595
Comm. 11-13-55

Comp. 12-12-55


Shot or Treated.

Contractor.

Issued. 2-4-56

County Pratt

KANSAS



Elevation. 1986 DF

Production. Dry

CASING:

9 5/8 @ 363' w/ 250 sx cmt.
7 in. 4564.72' w/ 160 sx cmt.

Figure 1. State Bottom of Formations.

clay & sand	202
sand & red bed	365
shale & shells	465
red bed & shale	734
sand & shale	1380
shale, shells & salt	1736
shale & shells	2001
lime	2437
lime & shale	3470
lime	3664
lime & shale	3970
lime	4394
lime & chert	4510
sand, shale & lime	4548
lime & shale	4588
lime	4595
Total Depth	

TOPS:

Heebner	3756
Toronto	3776
Douglas	3797
Brown lime	3940
Lansing-K. C.	3963
Drum	4121
Base K. C.	4320
Marmaton	4336
Mississippian	4422
Viola	4457
Simpson shale	4490
Simpson sand	4503
Arbuckle	4586

Perf. 4500-10, bailed 2 1/2 GW, no shows/
3 hrs. 500 gal acid, swb. 78 GO, 18.80
BW/5 hrs. set plug @ 4175'. Perf.
4122-25, bailed 6 GWPH, 500 gals.
Swb. 47 BW/7 hrs.. PB 4045. Perf.
3952-95, 3987-3990. bailed 2 1/2 GW/3 hrs.
500 gal. acid. test 16 GW, acid 1500
gal. then swb. 8.17 BW, no oil/6 hrs.
last 2 hrs. 1.17 BW.