

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

36-28-14W

Company- PHILLIPS PETROLEUM CO.
Farm- Tena No. 1


SEC. 36 T. 28 R. 14W
SE SE SW

Total Depth. 4655
Comm 7-24-54
Shot or Treated.
Contractor.
Issued. 10-16-54

PBTD 4623
Comp. 9-26-54

County Pratt

KANSAS



Elevation. 1986 DF

Production. IP 210 BO, 52 BW

CASING:
10 3/4 363' w/ 180 sx cmt.
7 in. 4650' w/ 250 sx cmt.

Figures Indicate Bottom of Formations.

sand & red bed	320
shale	365
shale & shells	662
red bed & shells	1046
shale & shells	2044
lime & shale	2164
shale	2249
lime & shale	2547
shale	2666
lime & shale	3323
lime	3384
lime & shale	3537
lime	3846
lime & shale	3988
lime	4411
lime & chert	4442
lime	4463
lime & chert	4530
sand & shale	4619
dolomite	4629
lime	4655
Total Depth	PB 4623

TOPS:
Heebner 3781
Toronto 3800
Douglas 3819
Brown lime 3960
Lansing-KC 3979
Base KC 4339
Mississippian 4443
Viola 4480
Simpson shale 4510
Simpson sand 4516
Arbuckle 4631

Perf 4569-73 w/ 6 §, acid 250 mud
acid & 250 gals, test 7.8 BO & 6 BW
5 hrs. set pluf 4558, dumped 1 sx
Calseal, FU 4555, perf. 20 § 4543-48,
bailed 20.12 BO & 7.98 BW-12 hrs.

Perf. 48 § 4526-38, swb 14.29 BO,
5.09 BW 6 hrs. Acid 250 mud acid.
Petrofraced, rec. 243.17 bbls fluid
after petrofrac