

WC

Field _____
 State Kansas County Kiowa
 Company Falcon Seaboard
 Farm Herring Well No. 1
 Sec. 15 Twp. 28S Range 16W
 _____ fr N _____ fr E _____ fr S _____ fr W
 of NW NW NE
 Contractor _____
 Remarks (Gulf Int)
 Comm. 9-11-55 Comp. 10-19-55
 Elev. 2148 T. D. 4821 P. B. _____
 Pay _____

I. P. 4,800 mcf R. P. _____
 Casing Record: 13 3/8 7
 20 10 3/4 5 1/2 4819/100
 16 98 5/8 396/300

9-14-55 <u>433.</u>		Tops	<u>sump</u>
SEP 21 1955	<u>Ø 3650</u>	<u>cho lvn.</u>	<u>Bm lvn. 4156</u>
SEP 28 1955	<u>Ø 4452</u>		<u>sump & 4172</u>
<u>DST 4674-85 open 40"</u>			
<u>4TS 1" Ø 3,500 MCF drop to</u>			
<u>3,000 mcf & held for 40"</u>			
<u>Ø 4720 rec 5' mud ns</u>			
<u>no press up</u>			
<u>Ø 4685-96 rec 6'</u>			
OCT 5th.	2' ss-sli fss. brn curbl shale - dead oil stain		
	v sh bleed gas		
	3' ss. as above ex. bleed oil & gas		
	1' chert breccia sh matrix dead oil stain		
<u>DST 4685-97 open 1 hr gd 610 TO</u>			
<u>rec 30' mud ns FP 44-48 GN 465/50</u>			
<u>Ø, ahead</u>			
OCT 5 1955	<u>Ø 4697-4715 1/2 rec 14 1/2'</u>		
<u>1 1/2' chert, puble breccia open sh</u>			
<u>matrix - shut bleed oil & gas. low perh.</u>			
<u>Ø 4716-20 - rec 4' as above</u>			

DST 4694-4720 (misc) apr 1 hr.
fr blo decreased to blk) res 15' m NS
all pres 0

Ø 4734-54 res 17'

1'5" chert cong - trace dead stain in face
2' sh. red & gray streaked - & mottled, waxy
5' chert pebs. breccia - Qtz pebs. sli to
very sdy in parts - some dead oil stain
some gel odor g & sli seat bleed out.
top 2' sh. gel seat stain bleed from pos

2'
2' clay-sh. rd-brn

2' chert peb breccia w vari sized cherts Qtz
pebs. sh matrix

2'5" chert cong. vari sized cherts Qtz
in sh clay matrix - sli sdy in part
oil stain in chert.

2' shale gray waxy - semi waxy, Cal
sdy in part
ran schl to 4821-

RTD 4821

5 ± 4819/100

OCT 12 1955: 2" tub^{WPK} @ 4600

ff 32/4680-88 sub NS

A/500 m sub & fls 1000 SI

2 m BD 5,000 m TP425

SIP 1400 # W

OCT 19 1955

cal of flu 4,800

SITP 1420 #

SIBH 1620 #

Log tops

Blk 3998

Bm Sm 4154

San KC 4170

Marm sd 4679

Marm fm 4686

Misc chert 4693

Kindenhook 4733

Vivian 4793

Ø