

MAP NO. \_\_\_\_\_ 2-1-61 ELEV. 2912GL, 2919 KB  
 STATE Kansas COUNTY Haskell SEC. 15 Twp 28S Rge 31W  
 OPERATOR Hamilton Bros., Inc., Amarillo, Texas LOC. C SE/4  
 WELL NO. 1-15 FARM NAME Mattie E. Henry FT. FROM \_\_\_\_\_ LINE  
 COL. Wildcat (PD 2755) FT. FROM \_\_\_\_\_ LINE  
 FR. 11-15-60 SPUD 11-12-60 COMP. 1-30-61 Skelly F/O

CONT./GEOL. Graham-Michaelis Tools  
 NAME PRODUCING INTERVAL FROM - TO PERF. W/HOLES TREATMENT RECORD  
 a Krider 2746-77 56 20,000 Ac  
 b \_\_\_\_\_ F/20x20  
 c \_\_\_\_\_  
 d \_\_\_\_\_  
 a I. P. OIL/DIST. \_\_\_\_\_ WTR. OF GAS 278 M.C.F.P.D. \_\_\_\_\_ CHK. 2" HRS. \_\_\_\_\_  
 b " " " " " " " "  
 c " " " " " " " "  
 d \_\_\_\_\_


SIP# 380 FI TP # 20 FI CP# \_\_\_\_\_ SIBHP \_\_\_\_\_  
 GR. \_\_\_\_\_ GR. \_\_\_\_\_ PBTD \_\_\_\_\_ TD 2786  
 SIZE DEPTH CASING - CEMENT RECORD SIZE DEPTH W/SAX.  
8 5/8" 648 500 \_\_\_\_\_  
4 1/2" 2785 700 \_\_\_\_\_

OPERATOR Hamilton Bros., Inc. WELL NO. #1-15 Mattie E. Henry ELEV. 2912 GL

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
Herrington	2716	203			
Upper Krider	2739	180			
Lower Krider	2763	156			

Spud 11-12-60, 8 5/8" @ 648 w/500 sx.  
 RTD 2786, E-Log, 4 1/2" @ 2785 w/700 sx. MICT.  
 P/(Krider) 16/2773-77, Frac 20,000-3% Ac X 20,000 sd.  
 P/(Upper Krider)/ 40/2746-56, 20,000-3% Ac, Max Ga 278 MCF,  
 FCP 20, SIP 380.  
 IP 278 MCF, FCP 20, SIP 380, from Krider (2746-77).  
 Shut in waiting on pipeline connection.  
 COMPLETE.

2919  
 2716  
 ---  
 203  
 2919  
 2763  
 ---  
 156  
 2919  
 2739  
 ---  
 180

LIBERAL TOPS

2919 KB

U/Krider 2738 (+181)  $\phi$  278 MCF  
RTD 2786

*Est. W 2805 +114*