

6-117W

MAP NO. 78

SEC. 15-28S-37W

STATE Kansas COUNTY Grant

LOC App SW SW NE

OPER. Lester Wilkinson, Wichita, Kansas

475 FT/FR west LINE

WELL #2 FARM Henthorn

100 FT/FR south LINE

POOL Hugoton

ELEV. 3056 GR. 3059 DF 3061 KB

CONT. Prime Drlg. Tools

GEOL. No geol. on test of NE/4

INT. 2700' Perm test

FR. 4/28/64

SPUD

4/29/64

COMP

6/9/64

TD 2648

FM.

L/FR

PBTD.

Completion Record

PRODUCING FM.

FROM

TO

PERF W/HOLES

TREATMENT

Chase

2392 - 2598

256

1500A & Frac

I.P. 72:20; 38,400,000 Cfgpd

Casing Record

10-3/4" @ 609

7" @ 2646

Data Inc.

KB Log Tops:

Holl	2365	+ 696	Win	2452	+ 609	RTD	2648	+ 413
Herr	2392	+ 669	U/FR	2525	+ 536	LTD	2648	+ 413
Kri	2414	+ 647	L/FR	2573	+ 488			

RTD 2648, 7" @ 2646, MICT, CO, Pf 48/2574-98 (Lower FR) 60/2526-5 (Upper FR) 68/2450-84 (Win) 80/2392-2432 (Herr) 1500 Gal,

15% Acid, Wash w/15,000 Gal 5% Acid + Frac (size not available)
Blew Down, cleaned up hole, 72-20: (5/21/64) 38,400,000 Cfgpd
CP 323#, Chase 2392-2598, COMPLETE (6/3/64)