

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


16-28-16N

Company- EL DORADO REFINING CO.  
Farm- Kinney No. 1

SEC. 16 T. 28 R. 16W  
NW NW SE

Total Depth. 4830  
Comm. 12-5-55 Comp. 12-23-55  
Shot or Treated.  
Contractor. Ben F. Brack Oil Co., Inc.  
Issued. 2-11-56

County Kiowa  
KANSAS



CASING:

8 5/8 365'  
5 1/2 4800'

Elevation. 2160

Production. 6,160,000 CFGPD

Figures indicate Bottom of Formations.

surface soil & shale	70
sand & gravel	160
shale	365
red bed & gypsum shells	430
white sand & gypsum shells	440
white sand & iron pyrite	455
shale & shells	1080
anhydrite	1110
shale & shells	1280
red bed, sand & shale	1810
shale, shells & sand	2025
shale & lime	2225
lime	2365
lime & shale	2450
lime	2674
lime & shale	2770
lime	2830
lime & shale	3005
lime	3130
lime & shale	3390
lime	3465
lime & shale	3640
lime	3750
shale & chalky lime	3852
lime & shale	3881
lime	4043
lime, shale & sand	4070
lime & shale	4144
lime	4700
lime & shale	4720
lime & chert	4754
lime	4783
shale w/ lime streaks	4814
lime	4830
Total Depth	

Douglas	4052
Brown lime	4180
Lansing	4196
Base K. C.	4516
Cherokee sand	4710
Mississippi	4726
Kinderhook	4762
Viola	4816
Arbuckle	4828

SCOUT TOPS:  
Heebner 4022  
Toronto 4038